

GABBERT-JONES, INC.

WILLIAMS "I" 3H
SEC. 19-33S-37W
STEVENS COUNTY, KANSAS

Drillers Well Log

COMMENCED: 7-3-89

COMPLETED: 7-6-89

OPERATOR: MATAGORDA ISLAND EXPLORATION COMPANY

DEPTH		FORMATION	REMARKS
From	To		
0	566	Sand - Clay	Ran 15 jts of 24# 8 5/8" csg
566	1055	Redbed	LD @ 627' w/215 sks 25/75
1055	1195	Shale	Posmix - 2% CC - 1/4# CF
1195	1363	Glorietta Sand	150 sks Common - 3% CC
1363	2340	Shale	1/4# CF.
2340	2910	Shale - Lime	PD @ 10:30 PM 7-3-89.
2910	2945	Lime	
	2945 TD		Ran 68 jts of 14# 5 1/2" csg
			LD @ 2940' w/210 sks Class C
			20% DCD - 2% CC - 1/4# CF
			40 sks Class C - 10% DCD
			2% CC - 1/4# CF
			PD @ 1:00 Pm 7-6-89.

STATE OF KANSAS]
]
COUNTY OF SEDGWICK]

I, the undersigned, being duly sworn on oath,
state that the above Drillers Well Log is true
and correct to the best of my knowledge and
belief and according to the records of this office.