


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

STEVENS COUNTY OIL & GAS CO.
Brubaker No. 1.

SEC. 34 T. 33 R. 37W
Cen NW $\frac{1}{4}$

Total Depth. 2777'
Comm. 1-23-39 Comp. 2-11-39
Shot or Treated. 1000 & 7000 Gals.
Contractor.
Issued. 5-6-39

County. Stevens



CASING:
12 $\frac{1}{2}$ " 582'9"
8 $\frac{3}{4}$ " 2573'

Elevation.

Production. 21,600,000 Gas
Figures Indicate Bottom of Formations. R.P. 412#

surface	35
sand & clay	125
sand gravel & clay	250
clay & sand	384
clay, sand & gravel	510
red bed & shale	588
red bed	645
sand, gyp & red bed	690
shale & shells	975
gyp	990
shale	995
sdv shale	1040
gyp	1145
shale & shells	1217
shale	1262
shale & sand	1340
shale, gyp & shells	1472
shale & shells	1703
brkn anhydrite	1731
anhydrite shale & shells	1921
gyp shells & shale	2012
shale & shells	2170
red bed & gyp shells	2263
anhydrite & shells	2435
brkn lime	2475
shale red & blue	2522
anhydrite & shale	2568
anhydrite & lime shells	2573
lime grey 1st sh gas 2573-78	2585
shale grey	2590
lime brkn	2600
lime grey 2nd sh gas 2600-08	2608
anhydrite	2623
shells grey	2625
lime grey 3rd sh gas 2642-70	2698
anhydrite 4th sh gas 2680-98	2702
lime grey 5th sh gas 2702-08	2712
shale grey	2715
red rock	2730
sdv lime	2738
lime grey	2777
Total Depth.	

Open flow natural 3,250,000 cu ft
Acidized w/1000 Gals. OF 4,400,000 Gas
Acidized w/7000 Gals.
After acidizing OF 21,600,000 Gas
R.P. 412#