

Stevens County, Kansas.

Sidwell & McCarthy, Crawford #1.

Loc: SW/4 31-33-37

Elev: 3135'-Altimeter

0	45	yellow surface clay
45	55	dry river sand
55	120	sandy clay
120	160	water sand-fresh water
160	225	river sand
225	440	quicksand, yellow- HPW 640-50'
440	565	river sand
565	690	red rock--HPW 640-50'
690	700	lime and gyp, hard, white
700	865	soft red rock
865	875	hard gray lime
875	883	soft red rock
883	890	red quick sand
890	984	soft red rock
984	1000	pink sand
1000	1085	red rock
1085	1135	hard white lime
1135	1160	red rock
1160	1175	hard white lime
1175	1180	red rock
1180	1271	river sand--water.
		Heaving sand-bailed 10" casing thru it. Mussell shells.
1271	1365	sand rock, light, very soft.
1365	1550	hard light sandy lime
1550	1555	light sandy lime
1555	1562	red rock
1562	1565	hard light lime
1565	1610	red sand
1610	1670	red rock
1670	1765	hard red lime
1765	1810	soft brown slate
1810	1845	red rock
1845	1905	sand. 5 lbs. water 1850-60'
1905	2240	red rock (Set 8" at 2095')
2240	2281	soft blue slate
2281	2285	hard white lime and quartz
2285	2390	soft blue slate. (gyp & anhydrite)

Casing Record:

127'	of	10"
578'	"	12 1/2"
622'	"	15 1/2"

(Incomplete)

REC'D.	MAY 23 1927
INDEX	
MAPS	
GRAPH.	
TYPED	
CC-S.F.	
FILE	