

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS


Location. Center NE $\frac{1}{4}$

Sec. 2 T. 33 R. 38W

Casing Record.

County. Stevens.

10" Farm. Spikes No. 1
 20" 8" Company. Texas Interstate Pipeline Co.
 15" 65/8" 2530 Contr.
 12" 586'4 53/16" Conn. 7-6-31 Comp. 8-4-31
 Total Depth. 2850 Shot Quarts Between.



Correspondence Regarding This Well Should Be Referred To.

Elevation. 3160

Figures Indicate Bottom of Formations.

Initial Production
 3,824,000 Cu ft Gas.
 R.P. 425#

Date Issued. 10-10-31

Formation	Depth.
sand	280
gravel	380
red bed	400
sand and gravel	544
red bed	653
GYP	685
gyp and sand	745
red bed	945
shells	1027
sand and gyp	1072
red bed and gyp shells	1668
gyp and lime shells	1718
lime hard	1740
red bed and gyp	1877
anhydrite and gyp	2061
lime and gyp	2098
shells hard red anhydrite & gyp	2145
lime and anhydrite	2180
lime and anhydrite and streaks of blue shale	2355
lime anhydrite and gyp	2400
anhydrite blue shale and gyp	2487
shale blue anhydrite lime shells	2495
shale red	2518
lime	2520

Finished Rotary July 22.

lime dark	2528
lime grey	2560
shale	2572
lime grey	2610
red rock	2612
lime	2660
red rock	2680
lime	2720
shale	2780
lime	2815
red rock	2820

Little sh gas 2545

Gas at 2615

Gas at 2650

Gas at 2680

2850 T.D. 10 ft cement in hole.

Finished Cable tools Aug 4th, 1931.