

**KANSAS DRILLERS LOG**API No. 15 — 189 — 20,195  
County Number

Operator

Anadarko Production Company

Address

Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

Bane "D"

Footage Location

1320 feet from (N) ~~XX~~ line 1320 feet from (E) (~~W~~) line

Principal Contractor

Earl F. Wakefield

Geologist

Spud Date

5-8-73

Total Depth

2990'

P.B.T.D.

Date Completed

6-16-73

Oil Purchaser


S. 8 T. 33S R. 38 W

Loc. C NE

County Stevens

640 Acres

N



Locate well correctly

Elev.: Gr. 3177'

DF KB

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	23#	518	Common	450	3% CC
Production	7-7/8	5-1/2	14#	2989	LiteWate Pozmix	500 150	12 1/2% Gilsonite/sk 18% Salt

**LINER RECORD****PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2936-41'
<b>TUBING RECORD</b>			2		2925-27'
Size	Setting depth	Packer set at			
2-3/8"	2801'		2		2787-2914' OA

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Acid w/750 gals 15% + 15 BS. Squeezed w/100 sx common.	2936-41'
Acid w/250 gals 15%.	2925-27'
Acid w/4000 gals 15% + 125 BS. Fraced w/120,000 gals wtr + 100,000# riversand.	2787-2927' OA

**INITIAL PRODUCTION**

Date of first production Not connected as yet		Producing method (flowing, pumping, gas lift, etc.) Flowing		
RATE OF PRODUCTION PER 24 HOURS	Oil  bbls.	Gas IWHOF 3032 MCF	Water  bbls.	Gas-oil ratio  CFPB
Disposition of gas (vented, used on lease or sold) Will be sold			Producing interval (s) 2787-2927 ' OA	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

perator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Well No. 1	Lease Name Bane "D"	Gas
S 8 T 33S R 38 W		

## WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

## FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Surf soil, sand & clay  
Red bed  
Red bed, anhy & sand  
Red bed & sand  
Sand, anhy & shells  
Anhy, shells & shale  
Lime  
Shale & lime  
Lime  
Total Depth

TOP	BOTTOM
0	475
475	517
517	1127
1127	1580
1580	1860
1860	2102
2102	2393
2393	2567
2567	2990
2990	

Logs:

Nuclear Log 1500-2983'

Council Grove top 2776'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Aug. 1973

RECEIVED  
STATE GEOLOGICAL  
SURVEY OF  
KANSAS

*T. W. Williams*  
T. W. Williams Signature

Division Office Supervisor

Title

July 20, 1973

Date