

KANSAS DRILLERS LOG

API No. 15 — 189 — 20,267
 County Number

S. 9 T. 33S R. 38 ^{NE}W
 Loc. 1250' FWL & 100' FSL
 County Stevens

Operator
Anadarko Production Company

Address
Box 351, Liberal, Kansas 67901


Well No. #1 Lease Name Farrar "B"

Footage Location
100 feet from (N) ~~SE~~ line 1250 feet from ~~SE~~ (W) line

Principal Contractor Gabbert-Jones, Inc. Geologist

Spud Date 3-9-75 Total Depth 2980' P.B.T.D.

Date Completed 4-3-75 Oil Purchaser



Locate well correctly
 Elev.: Gr. 3171.23'
 DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-/58"	20#	474'	Common	450	3% CC
Production	7-7/8"	4-1/2"	10.5#	2980'	Lite Wate Pozmix	575 150	4% gel 12-1/2# Gil 18% salt .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF		2938' -42'
			2 SPF		2796' -2922' OA

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/250 gallons 15% + 12 ball sealers.	2938' -42'
Acidized w/4000 gallons 15% + 135 ball sealers. Fraced w/120,000 gallons water + 100,000# Riversand.	2796' -2922' OA

INITIAL PRODUCTION

Date of first production SI for pipeline connection Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	COF 2410 MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Will be sold Producing interval (s) 2796' -2922' OA

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. #1 Lease Name Farrar "B" Gas

s9 T 33S R 38 K W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand	0	450		
Redbed	450	480		
Redbed-Sand	480	1500		
Shale-Anhy	1500	1884		
Shale w/Lime	1884	2191		
Lime-Shale	2191	2980		
Total Depth		2980		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

T. W. Williams
T. W. Williams Signature
Division Office Supervisor Title
April 16, 1975 Date