

KANSAS DRILLERS LOG

API No. 15 — 189 — 20,401
 County Number

S. 9 T. 33S R. 38 ^X_E
_W
 Loc. 1050' FNL & 1250' FEL
 County Stevens

Operator
 ANADARKO PRODUCTION COMPANY

Address
 P. O. Box 351, LIBERAL, KANSAS 67901


Well No. 2 Lease Name TROUP "B"

Footage Location
 1050 feet from (N) ^X_S line 1250 feet from (E) ^X_W line

Principal Contractor Lohmann-Johnson Geologist Joe Blair

Spud Date 4/13/78 Total Depth 6205' P.B.T.D. 6094'

Date Completed 6/14/78 Oil Purchaser



Locate well correctly
 Elev.: Gr. 3165.1
 DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1701'	Poz Common	600 200	4% gel, 2% cc 2% cc
Production	7-7/8"	4-1/2"	11.6#	6203'	SS Pozmix Lite Wate	170 400	.05% CFR-2 1/4# Tuff Fiber, 4%
					SS Poz	150	.05% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		6049-62'

Size	Setting depth	Packer set at
2-3/8"	6056'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1500 gals 10% MCA + 30 BS + 500 SCF N ₂ ; F/33,000 gals 75% foamed	6049-62'
3% acid + 33,000# 10-20 sand.	

INITIAL PRODUCTION

Date of first production SI for PL Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	2735 MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Will Be Sold Producing interval(s) 6049-62 (Morrow)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ANADARKO PRODUCTION COMPANY DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: GAS

Well No. 2 Lease Name TROUP "B"

S 9 T 33S R 38 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0'	40'		
Sand	40'	440'		
Redbed & Sand	440'	1085'		
Redbed	1085'	1150'		
Sand	1150'	1365'		
Redbed	1365'	1683'		
Sand	1683'	1699'		
Lime & Shale	1699'	6205'		
TOTAL DEPTH		6205'		
PBTD		6094'		

DST #1 6040-6099 (Morrow) 20 MPF w/strong blo w/GTS in 10 min, 20 min ga 1043 Mcfd, SI 60 min, tool open 60 min, 20 min ga 1357 Mcfd & stab, SI 120 min, rec 645' GOMCW, IFP 171-342, ISIP 1745, FFP 291-393, FSIP 1779, HP 3066-2949#.

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received

Paul Campbell
 Signature
 Paul Campbell, Division Production Manager
 Title
 June 19, 1978
 Date