

A-5-192
 MAP NO. _____ ELEV. 2014 DF
 STATE Kansas COUNTY Clark SEC. 4 Twp 33 S Rge 21 W
 OPERATOR Phillips Petroleum Company LOC. C SE NW
 WELL NO. 1 FARM NAME Wilson "A" FT. FROM _____ LINE
 POOL Sitka, NE Ext. (PD 5400) FT. FROM _____ LINE
 FR. 4-24-61 SPUD 4-20-61 COMP. 5-15-61

CONT./GEOL. Garvey Drilling Company
 COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM -- TO PERF. W/HOLES TREATMENT RECORD
 a _____
 b _____
 c _____
 d _____



D & A D & A (X)
 SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBTD _____ TD 5502
 CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8-5/8" 674 215

OPERATOR Phillips Pet Co WELL NO. 1 Wilson "A" ELEV. 2014 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Chase Group	2488		Heebner	4328	
Ft. Riley	2680		Toronto	4348	
B/ Florence Flint	2779		Lansing	4530	
Wreford	2845		Drum	4771	
Council Grove	2868		Base Kansas City	5034	
Cottonwood	3078		Marmaton	5048	
Neva	3095		Cherokee	5220	+
Wabaunsee	3389		Keyes Sand	5371	+
Tarkio	3531		Mississippian	5374	++
Topeka	3915		Ste Genevieve	5417	++
Heebner	4330				
Toronto	4347				
Lansing	4529				
Base Kansas City	4991				
Marmaton	5002				
Cherokee	5172				
Keyes Zone	5301				

Spud 4-20-61. 8-5/8" @ 674 w/215 sx.
 DST # 1 (Morr) 5286-5309, op 1 hr, rec 4 gal M, ISIP 70/30 min,
 FP 40-40, FSIP 55/30 mins.

5374
2014
-3360

A-5-192

SHEET NO. 2

MAP NO. _____

STATE Kansas COUNTY Clark SEC. 4 Twp 33 S Rge 21 W

OPERATOR Phillips Petroleum Company LOC. C SE NW

WELL NO. 1 FARM NAME Wilson "A"

DST # 2 (Morr) 5287-5334, op 1 hr, wk blo, rec 5 gal M/NS, ISIP
90/30 mins, FP 40-50, FSIP 60/30 mins.

RTD 5500, logs to 5502.

DST # 3 (Miss) 5327-5502, op 1 hr, GTS 55 mins - TSTM, rec 180'

SGCM + 180' WCM + 927' Mdy SW, ISIP 1835/30 mins, FP 70-490,
FSIP 1670/30 mins.

D & A 5-15-61

COMPLETE

OPERATOR

WELL NO.