


State Ks. Field KISMET, N.W.  
Company CABOT CARBON County SEWARD  
Farm NELLIE BURR No. 1  
Sec. 4 Twp. 33 S Range 31 W  
Spot 1980' fr N + 1973' fr W  
Contractor J.M. HUBER  
Remarks Superior E/o P.D. 6000' Miss



Comm. 7-3-58 Comp. 9-10-58  
Elev. 2783 DF 2775 GL 2775 KB TD 5990 PB  
Pay Marm (D.M.) 5031-41 38°  
MARM. oil discovery PLA 21/11/60  
pump & flood I.P. 171 BOPD Press.  
Casing Record: 13 3/8 7"  
20" 10 3/4 5 1/2" 5112/100  
16" 8 5/8 2350/1100

|                                    | Sample | Log                 |
|------------------------------------|--------|---------------------|
| <del>Spud log</del>                |        |                     |
| <del>φ ahead</del>                 |        |                     |
| <u>7-16</u> <del>φ 4240</del>      |        | HER 2595            |
|                                    |        | KRI 2652            |
| JUL 23 DST 4285-95                 |        | TORO 4282           |
| op. 30" Rec 10' M. D.M. 5018       |        |                     |
| EP 45-75 Choro 5188                |        | HER 2595            |
| SIP 1310/20" May 5538              |        | KRI 2662            |
| DST 4662-76 Op. 1" ss Maceo 5596   |        | TORO 4282           |
| GTS-4" 10"-88" KFC                 |        | CHES 5608 D.M. 5018 |
| 40"-44" MCF                        |        | CHERO 5188          |
| 1' - tstm                          |        | MOR 5538            |
| REC. 30' mud +                     |        | " ss 5596           |
| 960' xw, EP 65-360                 |        | CHES 5608           |
| SIP 1375/30"                       |        | HER 2594            |
| DST. 5020-32 Op. 75"               |        | KRI 2660            |
| GTS-6"                             |        | WIN+69 2712         |
| <u>7-30</u> 158 MCF/15" tstm-15"   |        | C.G. 2944           |
| REC. 2730' clean gassy oil (no tr) |        | b/HR 4278           |
| 34 38° FP 260-530, BHP 1160/20"    |        | TORO 4292           |
| DST 5350-84 lo Choro, op 2         |        | LAU-KC 4403         |
| Rec 20' M., all press-0            |        | CKB 4918            |
| <del>φ 5850</del>                  |        | D.M. 5029           |
| AUG 6 RTD 5990, Si, cng, WOC       |        | OSW 5090            |
|                                    |        | CHERO 5182          |

✓ Si fm tst @ 5053 Op. 21" 55 sec  
 Rec. .05 cu ft gas + 450 cc  
 wt. EP-165, SIP-1880  
 Si fm tst @ 5064 Op. 21" 53 sec  
 Rec. .07 cu ft gas + 4200 cc  
 wt. EP-95, SIP-1650

AUG 13 sat 52-4  
 P/40 MICT log? 5031-41 DM. 2' thg 5070  
 Swd. Id. Ac 250 Jma, Swbg  
 5 BUOPH - no wt  
 AUG 20 Swd 136 BNO-15', leak 6' - app. 7 BOPH  
 BOP

AUG 27 SEP 3 SEP 10  
 E pump + fluid 7.12 BNOBH-8'  
 calc. 171 BOPD  
 sty 38°

PXA 2/17/60

Log - Mm 5534  
 "ss 5598  
 -2815 5604  
 Ches. 5606  
 St. Gen. 5800  
 St. L. 5940  
 -3157

AMARILLO TOPS

2784 KB

- Winfield 2710 (-74)
- Heebner 4271 (-1487)
- Toronto 4280 (-1496) Tst'd Mud
- Lansing 4401 (-1617) Tst'd G&SW
- Marmaton 5028 (-2244) @ 171 BOPD
- Morrow 5536 (-2752) T 88', No sand
- Chester 5624 (-2840)
- St. Gen 5800 (-3016)
- St. Louis 5940 (-3156)