

WILDCAT

First Well for new
Discovery Allowable. ✓
90162

8-61W

Map No. K-82

OPER

ANADARKO PRODUCTION COMPANY

Liberal, Kansas

WELL

#1 LOW "B"

ONTR

Holm Drilling

WC

Disc (Cimarron Valley, SW)

IP

P 207 BOPD (Gr 53.9 deg) St L 5699-5702



S-T-R

19-33S-40W

SPOT

C NE NE

CO

MORTON, Ks.

ELEV

3275 KB 3765G

GR Log:

B/Cim 1498 +1767
Kri 2205 +1060
Win 2268 + 997
UFR 2332 + 933
LFR 2394 + 871
CG 2498 + 767
Wab 2920 + 345
Top 3155 + 110
Lan 3729 - 464
Chero 4566 -1301
Mrw Fm 5024 -1759
U/MrwSd 5184 -1919
B/U" " 5194 -1929
M/ " " 5336 -2071
B/ " " 5410 -2145
Mrw G" 5428 -2163

DST #1 (Mrw) 5190-5225, Op 1 hr, GTS 4", Ga 500,000
Cfcpd/4", Ga 650,000 Cfcpd/10", Ga 800,000 Cfcpd/15",
Ga 950,000 Cfcpd/25", Ga 1,000,000 Cfcpd/30",
Ga 1,150,000 Cfcpd/55", R 1' GCM, ISIP 1701#/23",
FP 175-328, FSIP 1701#/40"

DST #2 (Mrw) 5344-5406, Op 1 hr, GTS/23", Ga 1,500,000
Cfcpd - Stab - R 60' GCM, ISIP 1446#/30", FP 73-73#,
FSIP 1477#/40"

DST #3 (Mrw) 5406-5518 (Mrw), Op 45", GTS/9", Ga 500,000
/4", 850,000/13", 1,000,000/16", 1,020,000/20",
Ga 1,380,000/30", 1,400,000/40", R 250' GCM, ISIP 1497
/40", FP 175-429, FSIP 1446#/40"

RTD 5768 - Log - 5 1/2" @5762 w/300 sx

20/5725-30 (St L), § 160 BO + 123 BW/NT, nat,
§ 26 BO + 52 BW/NT, 12/5699-5702, pig @ 5710 & ran
2-3/8" tbg w/pkr @ 5690, § aver 6 1/2 BOPH/7 1/2 hrs, 5699-
5702, § 11.28 BO/1 hr, § 9.87 BO/1 hr, § 10.2 BOPH/NW/

Data Inc

6-3/4 hrs, Gr 49.8° @ 60°, tbg to 5707', SITP 56.4#/67
hrs, BHP 1588.3# @ 5701', BHT 152.7° - P 128BO + tr wtr
/16 hrs, P 188 BO + tr wtr/24 hrs. State Pot; P 207 BOPD
NW (Gr 53.9°) St L 5699-5702 COMPLETED 8-3-65

B/" G 5449 -2184
Miss 5523 -2258
Ste G 5551 -2286
St L 5696 -2431
LTD 5763 -2498

Spl (KB):

Mrw 5028
U " sd 5168
B/" sd 5208
Mrw G" 5428-52
B/Mrw 5452
Mrw G 5462
B/Mrw 5466
RTD 5768

MISC DATA

GEOL

FTG

SUPPT

CSG

L-S

ELEV. 3272 DF

3265 GR

SPUD DATE 6-15-65

DRLG COMP

FR by DATA 6-10-65

COMP by " 8-5-65

8" @1489' w/750 Sx, 5" @5762' w/300 Sx.

LIBERAL ELECTRIC LOG TOPS

3265 GL

Winfield 2268 (+997)
Council Grove 2526 (+739)
Topeka 3154 (+111)
Morrow 5024 (-1759)
"L" Sand 5184 (-919) 4/10
"S-3" 5334 (-2069) 0/8
"S-3" 5358 (-2093) 20/46
"S-3" 5428 (-2163) 16/22
Chester 5522 (-2257)
Ste. Genevieve 5594 (-2329)
St. Louis 5630 (-2365) ϕ 207 BOPD
TD 5768