


WILDCAT

STATE <u>KANSAS</u>	7-4-43 HP	MAP NO. _____	S-Y-R <u>26-33S-41W</u>	WF	
OPER <u>ANADARKO PRODUCTION CO</u>				SPOT <u>C NE NE</u>	INIT
<u>BOX 351, LIBERAL, KS</u>				CO <u>MORTON</u>	WF
WELL <u>1 MOORE "B"</u>				ELEV <u>3321 GR</u>	FIN
CONTR <u>DA MAC DRIG</u>					
FIELD <u>WC 2 MI SW CIMARRON VALLEY (MRW-MISS-ST L)</u>	GR LOG TOPS				
IP <u>DEA</u>					
<u>API 15-129-20138</u>					

SPUD 2-24-74, 8 5/8" @ 1455 w/700

No Cores

DST 1 (RED CV) 1450-1547, op30min, strong blow thruout,
 rec 633'MW, 120'SWCM, ISIP 436/45min, IFP 62-252,
 FFP 282-370, FSIP 436/45min

RTD 5800, log

DST 2 STRD (ST L) 5520-5665, op60min, rec 480'DM, NS,
 ISIP 1603/45min, IFP 206-183, FFP 275-321, FSIP 1420/
 45min

DST 3 STRD (MRW) 5220-72, op60min, rec 500'WCDM, 40'
 SW, ISIP 1283/45min, IFP 138-229, FFP 243-275, FSIP
 1283/45min

(CONT)

DST 4 STRD (KEYES) 5284-5422, op60min, rec 625'DM, NS,
 ISIP 1146/45min, IFP 390-413, FFP 413-413, FSIP 1100/45
 min

DST 5 STRD (U/MRW) 4842-5166, op60min, rec 658'DM,
 ISIP 1456/45min, IFP 275-802, FFP 413-505, FSIP 1283/
 45min

DST 6 STRD (CHER) 4559-4615, op60min, rec 400'SGCWM,
 w/RBSO, ISIP 367/45min, IFP 2060252, FFP 257-252,
 FSIP 275/45min

DST 7 STRD (KC) 4095-4158, op45min, rec 870'DM, NS,
 some plugging action, no pressures recorded

DST 8 STRD (TOP) 3125-55, op30min, GTS/3min, ga 18
 MCFG, decr to 7 MCFGPD/15min, rec 150'GCM, 180'
 MW, 600'wtr, ISIP 504/45min, IFP 252-310, FFP 252-43 6
 FSIP 504/45min

DST 9 STRD (TOP) 3143-54, op 60min, Ga 4 MCFG/10min,
 7 MCFG/20min, 8 MCFG/30min, second open -
 4 MCFG/10min, 4 MCFG/20min, 5 1/2 MCFG/30min, rec
 570'wtr, ISIP 480/45min, IFP 161-229, FFP 229-298,
 FSIP 482/45min

RTD 5800, 4 1/2" @ 2757 w/250

Completion data unsuccessful

DEA, COMPLETED 7-17-74

RED CAVE	1461 + 1860
COUNCIL GROVE	2448 + 873
TOPEKA	3089 + 232
HEEBNER	3524 - 203
TORONTO	3546 - 225
LANSING	3620 - 299
KANSAS CITY	3800 - 479
SWOPE	4144 - 823
MARMATON	4232 - 911
CHEROKEE	4474 - 1153
MORROW	4865 - 1544
L/MORROW	5137 - 1816
U/MORROW"G"	5206 - 1885



Petroleum Information
ESTABLISHED 1917
 COPYRIGHTED 1974 REPRODUCTION PROHIBITED

L/MORROW"G"	5243 - 1922
KEYES	5307 - 1986
CHESTER	5352 - 2031
STE GENEVIEVE	5394 - 2073
ST LOUIS	5534 - 2213
LTD	5805 - 2484
TD IN ST LOUIS	

COMP ISSUED 7-22-74