

2-175W
MAP NO. *K82*

3438 E Gr. ELEV. 3441DF 3443 EKB

STATE Kans. COUNTY Morton SEC. 16 TWP. 33S RGE. 41W

OPERATOR Thomas & Brewer LOC. C NE/4


WELL NO. 2 FARM NAME USA Unit *Gov.* FT. FROM _____ LINE

COL Berryman (Conf) FT. FROM _____ LINE

FR. 10/27/61 SPUD 10/27/61 COMP. 2/20/62

CONT./GEOL. Bennett & Roberts Tools

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Morr</u>	<u>5276-80</u>	<u>16</u>	<u>500A</u>
b			
c			
d			



Cal OF
d I. P. OIL/DIST. 0 WTR. 0 GAS 1690 M.C.F.P.D. _____ CHK. _____ HRS. 24

b " " " " " " " " " "

c " " " " " " " " " "

d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT 5300 TD 5450

CASING - CEMENT RECORD					
SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>1179</u>	<u>650</u>	<u>1 1/2" Tbg @</u>	<u>5260</u>	
<u>5 1/2"</u>	<u>5335</u>	<u>125</u>			

OPERATOR Thomas & Brewer WELL NO. 2 USA Unit ELEV. 3443 EKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums					
No Sample Tops			Kri	2211	+1232
			Winf	2255	+1188
RTD	5450	-2007	Morr	4898	-1455
			Miss	5400	-1957
DST #1 (Perm) 2220-75,			LTD (Miss)	Not available	

Op 1 hr., GB, R 90' SGCM,
IFP 21#, FFP 63#, FBHP 295#/30"

RTD 5450 (Miss) Log, 5 1/2" @ 5335 w/125 sx (DV Tool 2361)
 CO 5300, 3/5293 (Morr) 500A, Lost ld, 4/5270, Sq 5293 &
 5270 w/175 sx, CO 5305, 16/5276-80 (Morr) 1000A, Swb 2 1/2
 BWP/NT, Gas Ga 500 Mcfgpd, 48 hr. BD, Ga 1000 Mcfgpd + 30
 GWP/NT, Pkr 5260, 4/2282, Sq 150 sx, 4/2251, Sq 350 sx,
 8/2199-2200, Sq 150 sx, 8/2268-70 (Perm) 200A, \$ SG, TSTM
 8/2274-76 (Perm) 400A, \$ 25 GLWPH, 1500A, \$ 30 GLWPH/2 hrs
 w/ssg, Sq 2268-76/150 sx, CO 2300, 8/2274-76, 8/2262-64,
 8/2256-58, 600A, \$ 30 BLWPH w/sg, 2500A, \$ 120 GLWPH w/sg,
 12/2212-15, 8/2222-24 (Perm) PB 2240, 1000A (2212-24, \$ 1d
 NS, Re-set Plg @ 2330, 20,000A (2212-76) \$ 60 G 1d WPH w/SG
 Reset Plg 2345, Sq 2212-76, 400-sx, CO 5300 PBDT, 1 1/2" tbg
 5260 Cal OF 1,690 Mcfgpd, SIP 1288#, Morr 5276-80 COMPLETE

Win

Kri

LIBERAL ELECTRIC LOG TOPS

3442 KB

Krider 2210 (+1232)

Winfield 2257 (+1185)

Wabaunsee 2928 (+514)

Topeka 3172 (+270)

Heebner 3576 (-135)

Toronto 3592 (-150)

Lansing 3692 (-250)

Morrow 4898 (-1457)

"S-1" 4906 (-1465) 4/9

"S-2" 5025 (-1584) 15/17 NT

5 5198 (-1751) 3/12

"S-3" Z 5218 (-1777) 0/38 tite

"S-3" 5273 (-1832) 12/19; ϕ 1,690 MCF

"S-3" 5308 (-1867) 12/18

Keyes 5354 (-1913) 24/25

Keyes Jr. 5393 (-1952) 4/6

Chester 5399 (-1958)

TD 5450