


90495

9-248W
 MAP NO. _____
 STATE Kans COUNTY Morton SEC. 16 TWP. 33S RGE. 41W
 OPERATOR Thomas & Brewer LOC. C NE/4
 NO. 2 FARM NAME Government (OWWO) FT. FROM _____ LINE _____
Berryman Confirmation ELEV. _____ GR. 3441 0 DF. 3443 0 KB
 FR. 7/27/62 SPUD _____ COMP. 9/18/62

CONT. _____ /GEOL. _____
 NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD
 a. U/Morr (new zn) 5035 4 way jet 500A
 b. L/Morr (old zn) 5276-80 16 No new treat
 c. _____
 d. Co Pump (new zn) _____
 e. I. P. OIL/DIST. 95 B 0 WTR. NW GAS U/Morr M.C.F.P.D. no Gr CHK. _____ HRS. 24
 b. Old Pot: Cal OF 1690 MCFGPD (L.Morr) " " " " " "
 c. " " " " " "
 d. _____



D & A ()

SIPH _____ FI TP # _____ FI CPH _____ SIBHP _____
 GOR. _____ GR. _____ PBTD _____ TD 5450
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
 8 5/8" @ 1179 650 1 1/2" (tbg) 5260
 5 1/2" @ 5335 125 2" (tbg) 5046

OPERATOR Thomas & Brewer WELL NO. 2 Government ELEV. 3443 OKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
OWWO			KB Tops & Datums		
			Kri	2211	+1232
Old Info:			Winf	2255	+1188
			Morr	4898	-1455
			Miss	5400	-1957
			OTD (Miss)	5450	-2007

OLD INFO: (Same Operator) 5 1/2" @ 5335 w/125 sx. Comp 2/20/62.
 for Cal OF 1690 MCFGPD from lower Morr 16/5276-80 after, 500A.
 NEW INFO: Pull 2" tbg from pkr @ 5260 & set plg in pkr, 5 way
 jet @ 5035 (U/Morr) Swb & Flo 500 MCFGPD & 1 BOPH/NT, Nat.
 500 A, Swb 7 1/2 BOPH & 10% ld W/NT (No gauge on gas) 1 1/2" tbg thru
 @ 5260, & 2" tbg hung @ 5046, Swb 10 BOPH/NT from U/Morr
 (Dual Comp Upper & Lower Morr) P 95 BOPD, Morr 5035.
 Comp 9/11/62.

CORRECTION - Farm name was #2 U.S.A. Unit
 is #2 Government

See other Ticket