

WILDCAT

10-257W Map No. *K-82*

OPER SIDWELL OIL & GAS INC. - Pampa,
Texas

WELL #1 BORTH
Holm Drlg.

NC 1 1/2 mi W/Berryman (Wab Gas, Mrw Oil)

P. P 10 BOPD & 10 BWPD, Gr 40 deg, Mrw 5000-05

DST #1 (Wab) 2890-2925, Op 1 hr, R 30'M, ISIP 130#/30",
FP 32-43, FSIP 305#/30"

DST #2 (Top) 3293-3305, Op 1 1/2 hrs, 1320'GIP, R 30'HO&GCM
+ 60'HO&GCW + 240'GCSW, ISIP 524#/30", FP 70-192,
FSIP 490#/30"

DST #3 (Mrw) 4999-5010 Op 1 1/2 hrs, GTS/36", R 180'MCO,
ISIP 1599#/30", FP 53-83, FSIP 1446#/30"

RTD 5435' - Log *L* 4"@5148'w/150sx

CO 5100' 21/5000-05 (Mrw) No tst nat, 250MA, § 1d
w/so, Ga est 50,000 cfgpd, frac (5000 GO + 1250# sd) § 1d
w/sho new oil + est 50,000 cfgpd, § all 1d, § 4 BOPH
(26%wtr)/1 hr, Ga 126,000 cfgpd, SICP 1500#/12 hrs
POP P 88 BF/25 hrs (no breakdown) P 71 BO/24 hrs

P 30 BO + 35 BW/21hrs, P 17 BOPD + 60%wtr P 4-1/2 BO
+ 35 BW/17hrs, CP 50#, P 8.4 BO + 40% W/24 hrs, P 18-1/2
BO + 40%W/24 hrs, P 10-3/4 BO + 10 BW/24hrs

Co P 10 BOPD & 10 BWPD, Gr 40°, Mrw 5000-05 - COMPLETED
-25-65)



S-T-R 18-33S-41W

SPOT C NW NE

CO MORTON (Ks)

ELEV 3451 KB

KB Log:

Wab	2883	+ 568
Top	3133	+ 318
Hb	3549	- 98
Tor	3553	- 102
Lan	3595	- 144
Mrw	4870	-1419
U/" sd	4998	-1547
Mrw "G"	5244	-1793
Keyes	5287	-1836
Miss	5419	-1968
LTD	5419	-1968
RTD	5435	-1984

SpIs (KB)

Wab 2883

LeComp 3432

RTD 5435

Data Inc

*JS 3445 EDP
3437 GL*

MISC DATA GEOL Ralph Reynolds

ELEV 3448 DF

SPUD DATE 8-21-65

FTG _____

DRLG COMP _____

SUPPT Anadarko & CSO - Support

FR by DATA 8-16-65

CSG 8" @1491 w/500 sx. 4" @5148 w/150 sx.

COMP by " 10-28-65

LIBERAL ELECTRIC LOG TOPS

3448 KB

Wabaunsee 2884 (+564)

Topeka 3132 (+316)

Greenwood/Lansing 3442 (+6)

Heebner 3540 (-92)

Toronto 3560 (-112)

Lansing 3700 (-252)

Morrow 4870 (-1422)

"L" Sand 4988 (-1540) 10/18; \emptyset P 10 BOPD + 10 BWPD

"S-3" Sand 5242 (-1794) 18/24 NT

"S-3" Sand 5288 (-1840) 16/26 NT

Keyes 5338 (-1890) 20/24 NT

Keyes 5366 (-1918) 46/46+ NT

TD 5435