

90455



3-47W

MAP NO. K-82

SEC. 19-33S-41W

STATE Kansas COUNTY Morton

LOC. C NE SE

OPER. Thomas, Inc. - Liberal, Kansas

FT/FR _____ LINE

WELL #1 FARM Waddel

LS 3458

FT/FR _____ LINE

WC

ELEV. _____


GR. 3457

DF 3460 KS

CONT. Unit Drilling Co.

GEOL. Glen Thomas

INT. 5450' Miss Test



R. 2-18-65

SPUD. 2-15-65

COMP. 3-4-65

FD. 5430

FM. Miss

PBTD. _____

D & A

COMP. RECORD

WC-1 1/2 mi SW of Berryman (Wab Gas, Mrw O&G)

Data Inc.

8" @1495' w/600 Sx.

(KB Log Tops:)		<u>DST #1 (Purdy sd) 5036-60, Op 1 hr, GB/NT</u>
Mrw	4914 -1454	R 230' OCM, 1030' GCSW, No ISIP, IFP 80#,
Purdy sd	5028 -1600	FFP 600#, FSIP 1575#/30"
B/" "	5060 -1568	<u>DST #2 (Mrw) 5252-70, Op 1 hr, WB/8', died,</u>
Keyes	5392 -1932	R 1' M - All press 0#, <u>WLT #1 (Purdy sd)</u>
Miss	5424 -1964	5030-32 1/2, R 3400 cc form wtr / 1.1 cf "shot
LTD	5430 -1970	gas", FSIP 1700#/45", <u>WLT #2 (Purdy sd) 5035-</u>
(KB Spl Tops:)		<u>37 1/2, Op 90", R 2000 cc form wtr / 1.1 cf</u>
Purdy sd	5030	"shot gas", SP 50#, FSIP 50#,
D	5430	<u>DST #3 (Purdy sd) 5030-48, Strad pkr failed</u>

DST #4 (Purdy sd) 5032-50, (Str Pkr) Op 1hr, R 400' OCM, 1490' SW,
No ISIP, IFP 109#, FFP 516#, FSIP 1454#/30", RTD 5430, Ran Log,
D & A 2-28-65 - COMPLETED 3-3-65

LIBERAL ELECTRIC LOG TOPS

3458 DF

Winf. 2256 (+1204)

Wabaunsee 2912 (+546)

Topeka 3158 (+300)

Greenwood/Lansing 3462 (-4)

Heebner 3562 (-104)

Toronto 3580 (-122)

Lansing 3728 (-270)

Morrow 4914 (-1456)

"S-2" 5028 (-1570) 26/32 T O.G.C. m x w

"S-3" Zone ? 5250 (-1792) T 1' Mud

"S-3" Sand 5274 (-1816) 9/22 NT

"S-3" Sand 5328 (-1870) 38/42 NT

Keyes 5392 (-1934) 34+/34+ NT

TD 5430