


10-215W
 MAP NO. 82 SEC. 16 TWP. 33S RGE. 41W
 STATE Kans COUNTY Morton LOC. C NE SW
 OPERATOR Thomas & Brewer FT. FROM _____ LINE
 WELL NO. 4 FARM NAME Government FT. FROM _____ LINE
 Berryman ELEV. No GR. 3433 DF. 3435 E. KB.
 FR. 8/29/62 SPUD. 8/30/62 COMP. 10/16/62
 CONT. R. W. Rine Drlg. Co. /GEOL. _____



NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Purdy Sd</u>	<u>5032-46</u>	<u>32</u>	<u>Natural</u>
b			
c			
d			

State Pot: P

I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
<u>127 BO</u>	<u>NW</u>				<u>24</u>
b					
c					
d					

D & A ()

SIP#	FI TP #	FI CP#	SIBHP

GOR.	GR.	PBTD	TD
		<u>5090</u>	<u>5450</u>

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	DEPTH	W/SAX.
<u>8 5/8" @</u>	<u>1489</u>	<u>650</u>		
<u>4 1/2" @</u>	<u>5130</u>	<u>175</u>		

OPERATOR Thomas & Brewer WELL NO. 4 Government ELEV. 3435 EKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
(5100' Oil Tst)			KB Tops & Datums:		
RTD (Miss)	5450	10-2015	Morr	4912	-1477
			Purdy Sd	5026-67	-1591
DST #1 (Morr)	4905-35'	Op	Morr "G"	5200	-1765
	1 hr, WB 12", R 20' Mud,	Keys		5400	-1965
	IFP 20#, FFP 20#, FBHP	Miss		5428	-1993
	143#/30"				
DST #2 (Purdy)	5040-50'	Op	LTD	N.A.	
	60", GTS/3", Ga 500				
	Mcfgrp, TSTM in 60", R 2860' Oil + 270' SW, IFP 122#,				
	FFP 551#, FBHP 1382#/30".				
DST #3 (Purdy)	5050-70'	Op	1 hr, GTS 48", TSTM, R 180'		
	Oil + 30' OCM + 430' SW, IFP 115#, FFP 300#,				
	FBHP 1360#/30".				
RTD 5450, Log, Ran 4 1/2" @ 5130' w/175 sx, CO 5090,					
Perf 16/5032-36, 16/5042-46 (Purdy Sd), Swb 9 BOPH + 2%					
Wtr/NT, 2 3/8" Tbg 5080, POP. State Pot: Pump 127 BOPD/NW					
Purdy Sd 5032-46, 10/5/62.					

COMPLETED

LIBERAL ELECTRIC LOG TOPS

3435 KB

Winfield 2250 (+1185)

Topeka 3168 (+267)

Heebner 3578 (-143)

Lansing 3692 (-257)

Morrow 4910 (-1485)

"S-1" 4918 (-1493) 4/8; tst Mud

"L" Sand 5026 (-1591) 26/36; ϕ 127 BOPD

"S-3" Sand 5258 (-1823) 11/24; NT

"S-3" Sand 5296 (-1861) 8/20; NT

Keyes 5400 (-1965) 20/26; NT

Chester 5428 (-1993)

TD 5450