

11-85W

MAP NO. 87SEC. 16 TWP. 33S RGE. 41WSTATE Kans COUNTY MortonLOC. C SE NWOPERATOR Thomas & Brewer


FT. FROM _____ LINE

WELL NO. 2 FARM NAME Neptune

FT. FROM _____ LINE

OWNER BerrymanELEV. 3430 GR. 3437 DF. 3440 KBFR. 9/13/62 SPUD 9/12/62 COMP. 11/6/62CONT. R. W. Rine Drlg. Co. /GEOL. _____

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Purdy</u>	<u>5030-46</u>	<u>36</u>	<u>Nat</u>
<u>Co Pump</u>			



I. P. OIL/DIST.	95 BO	WTR. No	GAS	M.C.F.P.D.	CHK.	HRS.	24
"	"	"	"	"	"	"	"
"	"	"	"	"	"	"	"

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT _____ TD 5125

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>8 5/8" @</u>	<u>1495</u>	<u>625</u>			
<u>4 1/2" @</u>	<u>5124</u>	<u>150</u>			

OPERATOR Thomas & BrewerWELL NO. 2 NeptuneELEV. 3440 KB

SAMPLE TOPS

DEPTH

SUB SEA

ELEC. TOPS

DEPTH

SUB SEA

RTD(Purdy) 5125 -1685

KB Tops & Datums

(No other tops Picked)

Morr 4914 -1474

Purdy sd 5030-66 -1590

DST #1 (Morr) 5038-70, failed.

DST #2 (Morr) 5040-70, Op 1 hr., GTS/2", TSTM, R 450' oil + 450' SW, no IBHP, IFP 0#, FFP 465#, FBHP 1425#/30".

RTD 5125. Log. 4 1/2" @ 5124 w/150 sx.

Perf 20/5032-35, & 16/5042-46, (Purdy), Swb 5 BOPH/NW/NT. thru csg, nat, Swb 7 1/2 BOPH & tr wtr/NT, 2-3/8" @ 5054, Swb 5 BOPH/NW thru tbq. POP.

Co Pump 95 BOPD/NW, Purdy 5030-46.

COMPLETED

LIBERAL ELECTRIC LOG TOPS

3441 KB

Topeka 3174 (+267)

Heebner 3584 (-143)

Lansing 3698 (-257)

Morrow 4912 (-1471)

"S-1" 4922 (-1481) 4/10; NT

"L" Sand 5026 (-1585) 28/38; ϕ 95 BOPD

TD 5125