

90190

2-96W

Map No. 82



37.2

S.T.R. 13-335-42W

OPER CITIES SERVICE OIL CO.
GUYMON, OKLA.



SPOT C SW NE

CO MORTON (KS)

ELEV 3477 KB

#1 MINOR 'B'

LOHMANN-JOHNSON

DISC. OF BORTH WEST FIELD (MRW OIL)

I.P. STATE POT: P 37 BOPD + 1% WTR

MRW 4989-92

SPD 10-27-66 8-5/8" @1481/700 SX DON HUBER, GEOL

KB LOG TOPS:

WAB	2888+ 589
TOP	3135+ 342
HB	3520- 43
LAN	3615- 138
MRW	4864-1387
MRW"LL"SD	4986-1509
B/" " "	4994-1517
(4 FT POR)	
MRW SD	5144-1667
B/" " "	5200-1723
(NO POR)	
MRW SD	5232-1755
B/" " "	5300-1823
(62 FT POR)	
KEYES SD	5316-1839
B/" " "	5353-1876
(35 FT POR)	
CHEST	5353-1876
STE G	5494-2017
ST L	5595-2118
LTD	5762-2285
RTD	5762-2285

DST #1 (TOP) 3123-83, OP 1 HR, R 80'M (NO ISIP TAKEN)
FP 30-70#, FSIP 322#/30"

DST #2 (TOP) 3220-3327, OP 1 HR, GTS/6" TSTM, R 735'SW,
(NO ISIP TAKEN) FP 181-322#, FSIP 548#/30"

DST #3 (MRW) 4982-5002, OP 1 HR, R 180'OIL + 80'MCO + 10'
SW (GR 36.8 DEG) NO ISIP TAKEN, FP 48-110#, FSIP 1652#/30"

DST #4 (MRW) 5230-90, OP 1 HR, R 2173'SW, NO ISIP TAKEN,
FP 345-846#, FSIP 1060#/30"

RTD 5762' SCHLUMBERGER LOG 4 1/2" @5155/500 SX
MICT, CO 5127'PBD, GRN LOG, 12/4989-92 (MRW) § 5 1/2 BO
+ 1/3 BW/6 HRS NAT, 500A, § LD, § 18 BO + 5 BW/13 HRS,
§ 7 BO + 1/2 BW/4 HRS 2-3/8" TBG @5010 § 49 BO + 4 1/2 BW/24
HRS (GAS TSTM)(GR 36.8 DEG) (ALLOW 88 BOPD) POP

P 49 BOPD (GR 36.8 DEG) MRW 4989-92
STATE POT: P 37 BOPD + 1%WTR (GR 37.7 DEG) MRW 4989-92
(DISC OF BORTH WEST FIELD (MRW OIL) COMPLETED 2-14-67

GEOL DON HUBER

3475 DF
3467 GR

SPUD DATE 10-27-66

DRLG COMP

DATE DATA 10-20-66

DATE 2-16-67

8" 1481 W/700 SX. 4 1/2" 5155 W/500 SX.