

A-9-26

MAP NO. _____ ELEV. 3457 DF, 3451 GL

STATE Kansas COUNTY Merton SEC. 24 Twp 33S Rge 42W

OPERATOR Anadarko Prod. Company LOC. C. SW/4


NO. 1 FARM NAME Minor "A" FT. FROM _____ LINE _____

Greenwood Gas Area (PD 3420) FT. FROM _____ LINE _____

FR. 6-30-61 SPUD 6-30-61 COMP. 8-19-61

CONT./GEOL. Garvey Drilling

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM -	TO		
<u>Topeka</u>	<u>3118-3244</u>		<u>82</u>	<u>21,000 Ac</u>



a I. P. OIL/DIST. _____ WTR. WHOF GAS 1,420 M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " " " " " " " "

c " " " " " " " " " " " "

d " " " " " " " " " " " "

D & A ()

SIP# 303 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBD 3393 TD 3426

CASING - CEMENT RECORD		CEMENT RECORD		W/SAX.	
SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>13-3/8"</u>	<u>34</u>	<u>3 1/2 Yds</u>	<u>4-1/2"</u>	<u>3425</u>	<u>150</u>
<u>8-5/8"</u>	<u>642</u>	<u>400</u>			

OPERATOR Anadarko Prod. Co. WELL NO. #1 Minor "A" ELEV. 3457 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			B/Cimarron Anhydrite	<u>1442</u>	
			Wabaunsee	<u>2829</u>	
			Topeka	<u>3075</u>	
			Greenwood-Lansing	<u>3364</u>	

Spud 6-30-61. w/rat holer. 13-3/8" @ 34' w/3 1/2 yds. MIR. 7-10-61. 8-5/8" @ 642 w/400 sx.

RTD 3426, logs (Sj). 4-1/2" @ 3425 w/150 sx.

P/44/3222-44, 3000 Ac, 15 hr BD 750 MCF w/tr Wtr.

P/16/3176-84, 10/3143-48, 12/3118-24, set BP @ 3196. Ga 98 MCF,

3,000 Ac, 10 hr BD 1,209 MCF w/tr Wtr. CO to 3393. Trt 3118-

3244 w/15,000 Ac. 33 hr BD 1,209 MCF / 20 GWP. 20 min BD

3,400 MCF, dec to 2,636 MCF/40 mins.

IP WHOF 1,420 MCF, SIP 303, from Topeka (3118-3244).

COMPLETE 8-19-61.

LIBERAL LOG TOPS

3451 GL

Topeka 3076 (+375)¢ WHOF = 1,420 MCF
Greenwood/Lansing 3358 (+93)
TD 3427