


State Kansas Field Boehm
 Company C.S.O. County Norton
 Farm Mongone No. 2-Drill
 Sec. 23 Twp. 33 Range 42
 Spot 1390N 1/2 2340E of SW corner
 Contractor Hahn
 Remarks mor test
 Comm. 1-21-56 Comp. 1-30-57
 Elev. DF 3490 GL 3483 KB 3492 TD 5065 PB
 Pay 4836-56, 4814-32



I.P. 2,800 M.C.F. Press. 713
 Casing Record: 13 3/8 _____ 7"
 20" _____ 10 3/4 _____ 5 1/2" 4924/400
 16" _____ 8 5/8 1375/500

RUR	Sample	Log
NOV 27	TOP 2552	Ueva 2705
1500	CSOLan 3202	TOP 2991
8 3/8" @ 1375/500	Neob 3282	
3020	Lans 3418	
DEC 5	Marm 3717	
3020	chen 3901	
DST 3693-3782, op 1 hr.	At sd 4273	
Fr 6/6 T.O. Dec. TSTM,	Mor 4445	
REL 730' mud SW, FP 120-		
440, SP 860/45, HH 1980	S-3 4812	
LC 4329 regain	KeyPS 4917	
4380		
DEC 12		
DST 4540-86 failed		
DST 4576-93 "		
DST 4818-38, op 1 hr, gts 52"		
TSTM, rec 15' 9 cm FP 140-700, BHP 840/15, HH 2380		
DST 4830-4872, op 45" gts 4" 15" 9 57 MCF, 30" 9 1140 MCF		
45" 9 1190, 150' 9 cm FP 460-480, BHP 840/15,		
4870		
DST 4910-31, OP 75", rec 65' 9 cm, 2235' SW FP 210-1030		
BHP 1110/15		

Handed to
Prod oil

RTD 5065 ran log, prep to run csg.

DEC 19

5 1/2" @ 4924/400

WOST RULT CO 4857 PF 78/4836-56

71/4814-32 swab dry, sho gas. 12m BD 876 MCF
A/750m, A/1000, swabbing.

JAN 3

9 1/4" 426 MCF, fr/10,000, sd/6000, swab, kicked off
12m BD g 7,800 MCF, 20m BD g 7,830 MCF, killed well
ran 2" TC 4832, swab in. S.I.W.O.T.

JAN 9

SIP 671

5" OF 4,930 MCF, 20" OF 5,450 MCF

SWOST

JAN 16 ✓

JAN 28

JAN 30

Comp on 12m BD 7,800 MCF SIP 713
pA (S-3) 4836-56, 4814-32

Prod 390 MCF - went to oil

now 2-D

C

AMARILLO TOPS

3491 KB

Topeka 2941 (+550)

CSO Lansing 3198 (+293)

Heebner 3398 (+93)

Marmaton 3710 (-219)

Morrow 4486 (-995)

"S-2" 4582 (-1091) T 6', por 0'

"S-3" 4812 (-1321) T 49', por 27', tst'd 1,190 MCF

Keyes 4914 (-1423) T 44', por 41', tst'd XW

Chester 4958 (-1461)

TD 5062 (-1571)