

90191

A-7-33 82 ✓
MAP NO. _____
STATE Kansas COUNTY Morton SEC. 26 Twp 33S Rge 42W
OPERATOR Cities Service Petroleum Co. LOC. C NE NW
WELL NO. 1 FARM NAME Mongone "E" FT. FROM _____ LINE _____
POOL Boehm, Ext. (PD 5100) FT. FROM _____ LINE _____
FR. 5-22-61 SPUD 5-19-61 COMP. 6-23-61

3467KB
ELEV. 3465DF, 3458GL

CONT./GEOL. Lohmann-Johnson Tools

COMPLETION RECORD
NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
a Morrow 4885 Csg Notch 1500Ac, F/4X2

b _____
c _____
d _____
a I. P. OIL/DIST. Swb 131 BORD. GAS _____ M.C.F.P.D. _____ CHK. Swb HRS. 24
b " " " " " "
c " " " " " "
d _____

(C NENE ELW 3385 (ovv))

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
GOR. _____ GR. _____ PBTD 4903 TD 5130

CASING - CEMENT RECORD
SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8-5/8" 1374 900
5-1/2" 4946 100

OPERATOR Cities Service Petr. WELL NO. #1 Mongone "E" ELEV. 3467 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Topeka	2940		Topeka	2937	
Morrow	4488		Heebner	3398	
Morrow Sand	4778-84 ?		Marmaton	3704	
Morrow Sand	4860		Morrow	4488	
Keyes	4944-52		Morrow Sand	4774	
			Morrow Sand	4852-90	
			Keyes	4946	
			Chester	4998	
			Ste Genevieve	5112	

Spud 5-19-61. 8-5/8" @ 1374 w/900 sx.
DST #1 (Morrow) 4862-79, op 30 mins, Rc 3' M, FP 25-40, SIP 420/20 mins.
DST #2 (Keyes) 4946-62, op 1 hr, Rc 160' G&SWCM + 540' GCSW, FP 90-360, SIP 1025/30 mins.
RTD 5130, logs (Sj). 5-1/2" @ 4946 w/100 sx. MICT.
P/24/4882-88, Rc 2400' WIH. SQ 4882-88 w/150 sx. CO to 4903.
Cut csg notch @ 4885, 250 MA, Swb 200 GO + 150 GW/8 hrs, 250-15% Ac + 1000-7½% Ac, Swb 215 GO + 300 GW/8 hrs, Frac 4000 oilX 2000 sd. Rc 1d. Swb 97½ BNO/18 hrs. 2" tbg @ 4888.

IP Swab 131 BOPD (no water). From Morrow @ 4885.

LIBERAL TOPS

3467 KB

Topeka 2937 (+530)

Heebner 3398 (+69)

Marmaton 3704 (-237)

Morrow 4488 (-1021)

"S-2" 4774 (-1307)

"S-3" 4852 (-1385) 26/38; ϕ swb 131 BOPD

Keyes 4946 (-1479) 49/52

Chester 4998 (-1531)

St. Gen 5112 (-1645)

TD 5130