

3-296W
MAP NO. _____ SEC. 26 TWP. 33S RGE. 42W
STATE Kans COUNTY Morton LOC. App. W/2 SW NE
OPERATOR Cities Service Pet. Co. 1980 FT. FROM N LINE
WELL NO. 2 FARM NAME Mongone "E" 2130 FT. FROM E LINE
Boehm ELEV. 3420 GR. 3429 DF. 3431 KB
FR. 2-28-62 SPUD. 2-28-62 COMP. 3-27-62
CONT. Lohmann-Johnson Tools /GEOL.

COMPLETION RECORD
NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a _____
b _____
c _____
d _____
a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.
b " " " " "
c " " " " "
d _____

D & A

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
GOR. _____ GR. _____ PBTD _____ TD 5050

CASING - CEMENT RECORD
SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8 5/8" 1351 600

OPERATOR Cities Serv. Pet. WELL NO. 2 Mongone "E" ELEV. 3431 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

(KB Tops)

Top	2948	+ 483
Grnwd Lans	3215	+ 216
Hb	3352	+ 79
Lans	3428	+ 3
Marm	3736	- 305
Morr Form	4586	-1155
Morr sd	4878-86	-1447
Morr sd	4940-56	-1509
Morr sd	4968-5004	-1537

RTD(Morr) 5050 -1619

LTD(Morr) not available

DST #1(Lans) 3220-50 op.1 hr., gts/4", ga 240 Mcfgpd/5"
dec. to ga 44 Mcfgpd/60", R 60'VSO&GCM + 540'VSO&GCSW,
IFP 148#, FFP 225#, FBHP 355#/20"

DST #2(Morr) 4890-4910 op.30", R 2'M, IFP 15#, FFP 15#
FBHP 20#/30"

DST #3(Morr) 4972-5000 op.1 hr., R 100'VSGC salty mud, IFP
39#, FFP 77#, FBHP 901#/30"

RTD 5050(Morr) PGAC Log, LTD not available

D & A(3-17-62) COMPLETED

LIBERAL ELECTRIC LOG TOPS

3431 KB

Topeka 2948 (+483)

Greenwood/Lansing 3215 (+216) tst 44 MCF/1 hr + VSO&GCM +

Heebner 3352 (+79)

VSO&GCXW

Lansing 3428 (+3)

Marmaton 3736 (-305)

Morrow 4586 (-1155)

"S-2" 4878 (-1447) 0/8, tst mud

"S-3" 4940 (-1509) 0/16

"S-3" 4968 (-1537) 21/46, tst VSGCXM

TD 5050 D & A