


A-6-149

MAP NO. K-82 ELEV. 3670 KB
 STATE Kansas COUNTY Morton SEC. 30 Twp 33S Rge 43W
 OPERATOR Anadarko Prod. Co.-Liberal, Ks. LOC. C NE/4
 WELL NO. 1-30 FARM NAME Armstrong "A" * FT. FROM _____ LINE _____
 POOL Greenwood FT. FROM _____ LINE _____
 FR. 3-10-61 SPUD 3-8-61 COMP. 6-9-61



CONT./GEOL. Garvey Tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM	TO		
a				
b				
c				
d				

a	b	c	d	e	f	g	h
I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.		
b	"	"	"	"	"		
c	"	"	"	"	"		
d							

Temporarily Abandoned D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBDT _____ TD 3230

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>395</u>	<u>300</u>			
<u>4-1/2"</u>	<u>3222</u>	<u>200</u>			

OPERATOR Anadarko Prod. Co. WELL NO. #1-30 Armstrong "A" ELEV. 3670 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			<u>Wabaunsee</u>	<u>2716</u>	<u>+954</u>
			<u>Topeka</u>	<u>2936</u>	<u>+734</u>
			<u>Greenwood Lansing</u>	<u>3196</u>	<u>+474</u>

*Correct Farm name from Armstrong "B" to Armstrong "A".
 Spud 3-8-61. 8-5/8" @ 395/ 300 sx.
 RTD 3223, logs to 3230, 4-1/2" @ 3222 w/200 sx. MICT.
 P/4/2880-81. SQ/100. CO to 3197.
 P/20/3174-84, 500 Ac, Bld 72 GMPH, SQ 3174-84 w/50 sx.
 P/4/3140-42, 500 Ac, Swb 70 GFmWPH. SQ 3134-42 w/100 sx.
 P/10/3101-06, 500 Ac, Swb 50 GSWPH, SQ 3101-06 w/100 sx.
 P/8/3074-78, 500 Ac, Swb 300 GSWPH, had communication w/2880-81
 (SQ failed), ran tbg & pkr to 3050, 500 Ac, Swb 7 BSWPH.

Temp. Abandoned
COMPLETE 6-9-61.

liberal Tops

3665 G.h

Topeka 2938 (+127) N.T.

RTD 3223

Temp. Abnd


A-8-27

FIRST REPORT & COMPLETION

MAP NO. _____ ELEV. 3665 DF
 STATE Kansas COUNTY Morton SEC. 30 Twp 33S Rge 13W
 OPERATOR Anadarko Production Co. LOC. C NE/4
 WELL NO. 1-30 FARM NAME Armstrong "A" FT. FROM _____ LINE _____
 POOL Greenwood FT. FROM _____ LINE _____
 FR. _____ SPUD _____ COMP. 7-17-61

CONT./GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM	TO		
a				
b				
c				
d				



a	I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"	"
c	"	"	"	"	"	"
d						

Temporarily Abandoned

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBD _____ TD 3223

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD	SIZE	DEPTH	W/SAX.
<u>4-1/2"</u>	<u>3222</u>	<u>200</u>				

OPERATOR Anadarko Production Co. WELL NO. #1-30 Armstrong "A" ELEV. 3665 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			<u>Wabaunsee</u>	<u>2716</u>	
			<u>Topeka</u>	<u>2936</u>	
			<u>Greenwood Lansing</u>	<u>3196</u>	

Old Info: TD 3223. 4-1/2" @ 3222 w/200 sx.
 Was Temp. Abandoned 6-14-61.
 New Info: MICT. SQ 3074-78 (Top) w/50 sx. CO to 3050.
 P/6/3034-37, 500 Ac, Swb 5 BSWPH/NT. SQ 3034-37 w/200 sx. CO to 3030. Bld dry.
 P/20/3012-22 (Top), ran 2" tbg w/pkr, 500 Ac, Swb 2 BSWPH/9 hrs w/NS. SQ 3012-22 w/150 sx. CO to 3005, Swb dry.
 P/10/2991-96, 8/2974-78 (Top), Swb/NS, 1000 Ac 15%, Swb 3.3 BSWPH w/SS Gas. SQ 2974-96 w/200 sx.
 P/4 @ 1650. SQ w/150 sx.

Temporarily Abandoned.
 COMPLETE 7-17-61.

*Wad
 Anadarko
 Dropped lease*