


☆☆☆☆

State Kansas Field Greenwood
 Company PEPL County Morton
 Farm Campbell No. 1-32
 Sec. 32 Twp. 33S Range 43W

Spot C SE

Contractor Michaelis

Remarks



Comm. 9/1/56 Comp. 10-31-56

Elev. DF 3663 GL 3658 KB TD 3188 PB

Pay D & A

I.P. Press.

Casing Record: 13³/₈ 7" 630/175

20" 10³/₄ 5¹/₂"

16" 8⁵/₈

	Sample	Log
460		
SEP 19 <u>WGR.</u>		Wat 2708
SEP 19 <u>9970'</u>		Top 2921
SEP 26 DST 2892-2990 up 1 hr. 975 16"		True 3168
7 20" 44 MCF. 9 60 MCF in 1 hr.		3658
Rec 420' gcm. FP 135-190		510
BHP 500/20		
3044		
OCT 9 DST 3000-80 up 1 hr. 675 9"		
62 MCF in 20" 76 MCF in		
40" 80 MCF in 60" Rec 180' gcm.		
FP 45-90 BHP 455/20		
RTD 3188 1000 at 4 1/2 3136/250		
WOCT		
OCT 10 EVCT low GR by pf 64/3040-56 24/		
3076-82 A/4000 pf. 28/3006-13 ML 300'		
Sw in 3" ag w 350 hpt. pf. 56/2964-78		
A/1000 all sh gas + sw prep to sg.		
OCT 17 sg 250, Drill plug pf 28/2953-60 52/2985		
98, A/1000 15% ssho 9 + 75 g w/ph lot 9 255 MCF + 38%		
ret @ 2949, sg 125, CO		
OCT 24 PF 21/2953-60 A/1000. swab 150g sw ph sh sg		
sg/160. pf/48/2922-34 A/500 U.S.		
<u>Prep PF</u>		

OCT 31 Pf 32/2900-08 swab 12g sw/w TR 0
ret @ 2894 54/300. pf/16/2878-82
24/2864-70, A/500, swab 20g sw/w

D $\frac{1}{2}$ A

ϕ