

5-33-5W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DORSET COMPANY
Farm- Mason

No. 1

SEC. 5 **T.33**
 C SW NW

R5W

Total Depth. 4369'

Comm. 4-12-63

Comp. 6-20-63


Shot or Treated.

Contractor. Prime Drilling. Co.

Issued. 9-28-63

County Harper

KANSAS



Elevation. 1342' K. B.

Production. 19 BOPD_ N W

CASING:

8 5/8" 251' cem w/ 150 sx
 5 1/2" 4362' cem w/ 50 sx

Figures indicate Bottom of Formations.

clay & shale	82
sand	90
shale & lime	253
shale & anhydrite	605
shale & shells	960
lime	1300
lime & shale	1900
shale	2025
lime & shale	2422
shale & lime streaks	2575
lime & shale	2918
shale & lime streaks	3118
lime & shale	3268
shale & lime	3441
lime	3470
sand	3546
shale & lime	3710
lime	4030
lime & shale	4234
shale & lime	4281
shale	4349
lime	4363
lime	4369
Total Depth	
TOPS: SMP	
Stalnaker Lime	3440
Kansas City	3702
Mississippi	4365