

14-33-5W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ARVEL C. SMITH
Farm- Armstrong No. 1

SEC. 14 T. 33 R. 5W
NE NE SW

Total Depth. 4966'
Comm. 3-29-61 Comp. 4-22-61
Shot or Treated.
Contractor. Red Tiger Drlg. Co.
Issued. 7-22-61

County Harper
KANSAS



CASING:
8 5/8" 235' cem w/175 sx.

Elevation. 1297' DF

Production. Dry

Figures Indicate Bottom of Formations.

red sandy shale	40
sandy clay	85
clay, shale & gyp	185
blue shale	235
blue shale, red shale	465
shale	948
Anhydrite	973
shale & shells	986
lime	1040
shale & lime	3470
sand & shale	3517
shale & lime	3805
lime	3993
lime & shale	4090
lime	4158
lime & shale	4210
lime	4319
lime & shale	4425
cherty lime	4464
lime, chert & shale	4490
lime	4512
cherty lime	4632
sandy lime	4664
cherty lime	4816
lime & shale	4911
shale, Simpson sand	4921
shale, sand	4930
Simpson sand	4948
shale, sand	4965
sand	4966
Total Depth	
TOPS: SCOUT	
Heebner	3094
Toronto	3128
Douglas	3212
Stalnaker Sand	3468
Kansas City	3723

Base Kansas City	3945
Marmaton	4057
Cherokee	4243
Mississippi	4441
Kinderhook	4825
Simpson	4918