


6-44W Map No. K-84
OPER CABOT CORP - PAMPA, TEXAS

WELL #1 HARRELL UNIT

Y K-T-M DRLG. INC.

FIELD EVALYN-CONDIT (MAR-MRW-MISS)

I.P. FLO 400 BOPD + TR WTR, GR 39, MRW 5635-41



S-T-R 5-33S-33W

SPOT C SW SW ✓

CO SEWARD (KS)

ELEV 2813 KB

(LOG)

MRW 5556 -2743

" SD 5634 -2821

B/SD 5642 -2829

CHES 5778 -2965

STE G 6102 -3289

ST L 6224 -3411

LTD 6324 -3511

(SPL)

MRW 5580

MRW SD 5632

B/SD 5640

RTD 6324

SPUD 4-16-66 8" 1603 W/66 SX.

JOHN ROSS - GEOL

DST #1 (MRW) 5634-46, OP 60", GA 33,700 CFGPD/10", GA
28,000 CFGPD/20", GA 12,000 CFGPD/30", DECR TO TSTM, R
1800' FO (GR 38) + 10' HO&GCM, ISIP 1802#/30", FP'S
81-501#, FSIP 1783#/45"

DST #2 (MRW) 5758-67, OP 90", R 5' M, ISIP 0#/30", FP'S
16-21#, FSIP 21#/30"

RTD 6324, 4½" 5736 W/150 SX.

MICT PF 24/5635-41, 250A, 8 DN, SO, FRAC 15,000 GAL
+ 15000# SD, 8 WELL, FLO 135 BO/NT, CUT W/30% FRESH WTR,
CP 350#, TP 40#, 48/64" CHOKE,

STATE POT: FLO 400 BOPD + TR WTR, GR 39, MRW 5635-41 -
COMPLETED (6-1-66)

Data Inc

MISC DATA

GEOL JOHN ROSS

FTG E-log

SUPPT

CSG 8" 1603 W/66 SX. 4½" 5736 W/150 SX.

ELEV 2803 GR

SPUD DATE 4-16-66

DRLG COMP

FR by DATA 4-4-66

COMP by " 6-2-66

L-S 7803 Gr

LIBERAL ELECTRIC LOG TOPS

2813 KB

Winfield 2646 (+167)

Heebner 4164 (-1351)

Toronto 4182 (-1367)

Lansing 4296 (-1483)

Marmaton 4970 (-2157)

Morrow 5544 (-2731)

5632 (-2819) 4/12; $\emptyset$ Flo 400 BOPD + tr wtr.

5664 (-2851) 0/18

5712 (-2909) 0/10

"S-3" Sand 5754 (-2941) 6/16

Chester 5770 (-2957)

5800 (-2987) 4/20

Sand 5992 (-3179) 0/14

Ste. Gen 6096 (-3283)

St. Louis 6228 (-3413)

TD 6324