

Geological Report

American Warrior Inc.
Pulliam #1-35
500' FSL & 940' FWL
Sec. 35 T33S R6W
Harper County, Kansas

James Dilts
Geologist

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS

American Warrior, Inc.

General Data

Well Data:

American Warrior Inc.
Pulliam #1-35
SE-SW-SW
500' FSL & 940' FWL
Sec. 35 T.33S R.6 W.
Harper County, Kansas
API # 15-077-21, 598-0000

Drilling Contractor: Duke Drilling Co

Spud Date: 10/31/2007

Rotary TD Date: 11/11/2007

Rotary TD: 5026'

Elevation: 1278' Ground Level
1289' Kelly Bushing

Casing: Surface 211' 8 5/8" 24# surface casing set at
223' w/185 sx 60/40 3%cc
Production 5.5" 15.5 # 4727' @ 4727' w/165 sx
AA2 1/4# Flocele

Samples: 10' wet and dry, 2000' to RTD

Drilling Time: 2000' to RTD

Electric Logs: DIL/CDL//BHCS/CNL

Drillstem Tests: Three

Problems: None

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS

Formation Tops

Pulliam 1-35

Heebner	3136'-1847
Toronto	3158'-1869
Brown Lime	3502'-2213
Kansas City	3788'-2499
BKC	4024'-2735
Marmaton	4098'-2809
Pawnee	4204'-2915
Ft Scott	4230'-2941
Cherokee	4236'-2947
Mississippi	4450'-3161

DST 1: Kansas City

Interval (3789'-3820') Anchor Length 31'

I.F Weak Blow 1/4"	IF 18-20#
I.S.I No Blow	ISI 162#
F.F Weak Blow 1/4"	FF 24-27#
F.S.I No Blow	FSI 132#

Recovery: 30' SOCM %gas 1%oil 99%mud

DST 2: Mississippi

Interval (4450'-4461') Anchor Length 11'

I.F BOB 5.5 Min	IF 23-61#
I.S.I No Blow	ISI 1563#
F.F BOB 44 Sec	FF 52-84#
F.S.I No Blow	FSI 1558#

Recovery: 98' GM&OCW 12%gas 28%oil 40%w 20%mud
122' GM&WCO 15%gas 55%oil 5%w 5%mud

DST 3: Simpson

Interval (4915'-4937') Anchor Length 22'

I.F BOB 8 Min	IF 46-276#
I.S.I No Blow	FSI 2012#

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS

**F.F BOB 12 Min
F.S.I Weak Blow 1.5''**

**FF 283-377#
FSI 2009#**

Recovery:

320' SWCM	%gas	%oil 10%w	90%mud
400' SMCW	%gas	%oil 90%w	10%mud

Summary: Due to structural position and log information, the decision was made to case the Pulliam 1-35 for further evaluation

Respectfully Submitted,
James F Dilts

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS