

26-33-6W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **SUNRAY DX OIL CO.**
 Farm- **D. Meineke** No. **1**

SEC. 26 T. 33 R. 6W
 C NW SE

Total Depth. **4881'**
 Comm. **12-20-62** Comp. **1-8-63**
 Shot or Treated.
 Contractor. **Gravey Drlg. Co.**
 Issued. **7-31-65**

County **Harper**
KANSAS



CASING:

Elevation. **1279 RB**

8 5/8" 260' w/225 sx cem.
5 1/2" 4477.61' w/100 sx cem.

Production. **Flo. 1,860,000 CFG**

Figures Indicate Bottom of Formations.

surface clay	60
surface clay, sand, shale	261
shale shells	984
Anhydrite	1016
shale, shells	1050
lime, shale	1380
lime	1835
shale, lime	2040
shale, shells	2065
shale, lime stks	2465
shale, lime	2590
shale, shells	2835
lime, shale	3770
lime	3850
shale, lime	3885
lime, chert	4035
lime	4417
Mississippi	4455
lime, Mississippi	4497
Mississippi lime	4725
lime	4780
cherty, lime, shale	4817
lime, shale	4858
Simpson	4881
Total Depth	

TOPS: SCOUT	
Heebner	3106
Lansing	3474
Stalnaker	3506
Kansas City	3766
D/Kansas City	3998
Marmaton	4062
Cherokee	4238
Mississippi	4380
Kinderhook	4760
Simpson	4854