


16-33-7W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY LEE PHILLIPS OIL
FARM Blasdel NO. 1

SEC. 16 T. 33 R. 7W
LOC. C NE NE

TOTAL DEPTH 4980'
COMM. 11-24-67 COMP. 12-14-67
SHOT OR TREATED
CONTRACTOR Sweetman Drlg.
ISSUED 1-27-68



COUNTY Harper
KANSAS



CASING
20 10
15 8 5/8" 210' cem w/ 175 SX
12 6
13 5

ELEVATION 1345' KB
PRODUCTION DRY/ SIMP

FIGURES INDICATE BOTTOM OF FORMATIONS

0	50	Red Rock
10	210	Red Bed
210	2130	Shale & Lime
2130	2487	Shale
2487	3130	Lime & Shale
3130	3630	Shale & Lime
3630	3800	Sand & Shale
3800	3955	Lime & Shale
3955	4156	Lime
4156	4380	Lime & Shale
4380	4503	Shale & Lime
4503	4639	Lime
4639	4867	Lime & Shale
4867	4931	Lime
4931	4931	Shale
4931	4954	Lime & Shale
4954	4980	Sand
4980		Total Depth

TOPS: LOG

Chase	1445
Heebner	3316
Iatan	3627
Stalnaker	3634
Kansas City	3930
Base Kansas City	4165
Marmaton	4220
Cherokee	4350
Mississippi	4503
Osage	4570
Kinderhook	4832
Viola	4926
Simpson Dolomite	4952
Simpson sand	4959

T. D. Sweetman, Partner of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman