


State Ks. Field Massoni
Company Cabot Carbon County Seward
Farm Robbins Unit No. 1
Sec. 7 Twp. 33S Range 31W

Spot 1980 fm N + 2080 fm E

Contractor Graham - Michaelis

Remarks C.C. 75% P.D. 6000
North Nat 25%



Comm. 12/17/58 Comp. 2/11/59

Elev. 2766 DF 2762 GL 2758 KB 6008 TD 6008 PB

Pay DTA

I.P. DTA Press.

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 6008/300

16" 8 5/8 2346/1100

Log	Sample	Log
DEC 17 RURT	Her 2552	Her 2552
DEC 30	Kri 2624	Kri 2620
JAN 7 2p. log.	Win 2692	CG ⁻¹⁴⁶ 2912
55535	B/Hb 4244	Tor 4262
JAN 14 E 5557-5607	Tor 4252	Lan ⁻¹⁶¹⁴ 4380
rec 50'	Lan 4380	ChB 4866
20' sh, gray	ChB 4866	Mm 5028
5 1/2' ls, xtn, tite bldgs	D.M. 5018	Osw 5146
7 1/2' sh, gray	Osw 5140	Cher 5200
17' ss silty w/ gas odor	Cher 5176	Mor ⁻²⁷³⁴ 5520
D&T 5500-5607	Mor 5518	ss ⁻²⁸²⁶ 5592
90 37" rec 80' m FP	Miss 5626	⁽⁴⁾ 5606
0-55 SIP 55/30		Ch ⁽⁻²⁸⁶¹⁾ 5627
E 5607-26 rec 19'		St. ⁽⁻³⁰³²⁾ 5748
12' sh gray, calc.		St. L. ⁻³¹⁴⁶ 5912
7' sh, line nodules		
E 5626-54 rec 13'		
6 1/2' sh, gray,		
1/2' ls gy, xtn,		
4' sh		
2' ls gray, dng, xtn,		
remaining E hole		

JAN 21 RTO 5980 S; to TO
DST 5900-80 up 1'05" rec 480'
hgc + sli 00 m FP 245-295
BHT 51P / 2150/30 & deeper
to 6008 no rerun of leg ~~csj~~

~~WOC~~
JAN 28 MI legs, P62/5990-6008
sub N.S. A/500 m, subd.
pl @ 5986 P40/5950-60 subg.
~~prep to Ac.~~

FEB 4 A/500 m sub 2 1/2 BXWPH + tr OLG
br pl @ 5790 P24/5386-92
52/5600-13 A/500 m sub sli
tr Fx 21 rw x 20 sd flush 240
BW subg w/NS.

FEB 11 subd & ba dry gas to fm

D+A

AMARILLO TOPS

2764 KB

Winfield 2654 (+110) 2675 (+89)
Heebner 4240 (-1476)
Lansing 4379 (-1615)
Marmaton 5022 (-2258) T 110',
Morrow 5520 (-2756) T 110'
Chester 5630 (-2866)
St. Gen 5772 (-3008)
St. Louis (Opr) (5912)
TD 5982 (-3218)