

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

12-33-8W

Company. SKELLY OIL CO.
Farm. Alfred Miller No. 1

SEC. 12 T. 33 R. 8W
NW NW SW
330' fr NL, 330' fr NL, NW/4

Total Depth. 5004.5

Comm. 11-13-55


Comp. 12-3-55

Shot or Treated.

Contractor. Chas. Hulme Drilling Co., Inc.

Issued. 1-14-56

County **Harper**
KANSAS



Elevation. 1371 DE

Production. Dry

CASING:

8 5/8 @ 315' w/ 250 sx cmt.

Figures indicate Bottom of Formations.

surface soil & sand	40
red bed & shells	315
red bed & shale	815
shale & shells	1375
lime	1705
shale & lime	2640
lime	2760
shale & lime	2890
shale	3065
lime	3165
lime & shale	3475
shale	3705
shale & sand	3820
lime	4155
lime & shale	4210
lime	4480
lime & shale	4498
white opaque slightly tripolitic chert	4512
chert	4641
lime	4700
chert	4731
sandy lime	4775
chert	4798
shale & lime	4867
shale	4894
cored. rec. 32'	4926
lime & shale	4984
shale & sand	5004.5
Total Depth	

open 1 hr. strg. bl. thruout, rec. 70' wtry mud, 3255' SW, IFP 350#, FFP 1500#, BHP 2000#/20 min.

TOPS:	
Kansas City	3958
Base K. C.	4169
Marmaton	4240
Cherokee	4400
Mississippi lime	4500
Kinderhook	4814
Misener sand	4902
Viola lime	4910
Simpson dolomite	4948
Simpson sand	4985

Ran Halliburton Gamma Ray Survey
Guard Log

DST #1: packer @ 4493, open 1 hr. very wk. bl. air 35 min. rec. 20' drlg. mud. IFP & FFP 10#, BHP 35#/20 min.

DST #2: packer @ 4898, 28' anchor, open 30 min. very light bl. air 22 min. rec. 12' rotary mud, IFP & FFP 25#, BHP 55#/20 min.

DST #3: packer @ 4983, 21½' anchor,