


WELL RECORD

30-33-8W

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Lonker "A" Well No. 1
 Well Located: NE SE SW
SEC 30 TWP 33S RGE 8W
 Operator: McCoy Petroleum Company
 Address: 502 Union Center, Wichita, Ks 67202
 Elevation: Ground 1304 D.F. 1309 K.B. 1312
 Type Well: (Oil, gas, dry hole) Dry hole

Drilling Commenced: November 21st 71 Drilling Completed: November 12th 71
 Well Completed: November 12th 71 Total Depth 4888'
 Initial Production: D & A

Casing Record

Size: 8-5/8" Set at 255' Size: _____ Set at _____
 Size: _____ Set at _____ Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8-5/8"</u>	<u>185</u>	<u>Common</u>
_____	_____	_____
_____	_____	_____

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)


Dresser-Atlas GR-N-LL-C Surface to TD

30-33-8W

Formation Top Bottom

Show Drill Stem Tests,
Well Stimulation and
Production Tests

30-33-8w



DRESSER ATLAS LOG TOPS

Base LeCompton	3152(-1840)
Heebner	3345(-2033)
Douglas Sand	3394(-2082)
Iatan	3640(-2328)
Stalnaker Sand	3660(-2348)
Kansas City	3958(-2646)
Stark Shale	4098(-2786)
Cherokee Shale	4350(-3038)
Mississippian Conglomerate	4464(-3152)
Spergen-Warsaw	4472(-3160)
Osage	4516(-3204)
Kinderhook Shale	4731(-3419)
Viola	4812(-3500)
Simpson Shale	4882(-3570)
Simpson Sand	4885(-3573)
Log Total Depth	4888(-3576)

DRILL STEM TESTS

Stalnaker

DST #1 3643-3705'.

Open 30", S.I. 30", open 30", S.I. 30".
Good blow throughout test.
Recovered 1080 feet of saltwater.
IBHP 1515# FBHP 1515#
IFP 70#-370#, FFP 400#-500# HH 1922# BHT 115°.

Mississippian

DST #2 4475-4500'.

Open 30", S.I. 45", Open 30", S.I. 45".
Good blow throughout test.
Recovered 60 feet of mud.
IBHP (False) FBHP 1243#
IFP 31#-31# FFP 31#-31# HH 2428# BHT 127°.

Mississippian

DST #3 4500-4530'.

Open 30", S.I. 30", Open 60", S.I. 30".
Recovered 1900 feet of gas in the pipe,
100 feet of gas cut mud and
50 feet of watery mud.
IBHP 1521# FBHP 1274#
IFP 47#-66# FFP 66#-114# HH 2454# BHT 128°.

Viola

DST #4 4816-4840'.

Open 30", S.I. 30", Open 30", S.I. 30".
Very weak blow throughout test.
Recovered 90 feet of muddy water.
IBHP 1633# FBHP 1538#
IFP 54#-54# FFP 54#-54# HH 2630# BHT 134°.

30-33-8w