

5-241W + MAP NO. 84 SEC. 8-33S-33W
 STATE Kansas COUNTY Seward LOC. C SW NW

OPER Cabot Corporation, Pampa, Texas FT/FR _____ LINE _____

WELL #1 FARM H. C. Bryant "A" LS FT/FR _____ LINE _____

March ELEV _____ GR. 2845 DF 2848 KB _____

NT Rine Drlg. Tools, rig #2 GEOL. Doug Marden

CO. INT. 6350' test

F.R. 3/9/64 SPUD 3/12/64 COMP. 5/26/64

TD 6381 FM St. Louis PBTD. _____

PRODUCING FM. FROM — TO PERE W/HOLES TREATMENT

Morrow 5678 3 way Jet 250A

I.P. Gauge 6,640,000 Cfgpd (SITP 1040#)

8-5/8" @ 2750 w/200 sx. DV Tool @ 531 w/400

5 1/2" @ 6019 w/200 sx.

KB Spl Tops: KB Log Tops:

B/Hb	4182	-1334	Kri	2590	+ 258	Ckrbrd	4835	-1987
Tor	4214		Winf	2677	+ 171	Marm	5036	-2188
Lans	4335		L/FR	2791	+ 57	Cher	5190	-2342
Ckbrd	4838		CG	2931	- 83	Mrw	5608	-2760
Des M	4974		Tor	4217	-1369	Up Mr sd	5655	-2807
er	5221		Lans	4336	-1488	B/" " "	5682	-2834
RTD	6380	-3532						

DST #1 (Mrw) 5656-67, GTS/2", Ga 5,000,000	L Mr sd 5822	-2974
Cfgpd, Op 30", Ga 1,024,000 Cfgpd/2",	B/L " "	5834 -2986
Ga 7,684,000 Cfgpd/11", Ga 8,544,000	Chest	5858 -3010
Cfgpd/17", Ga 8,544,000 Cfgpd/30", R 2'	Chest sd	6050 -3202
Cond, ISIP 1727#/30", IFP 1388#,	B/sd	6062 -3214
FFP 1367#, FSIP 1705#/45"	St Gen	6155 -3307
DST #2 (Mrw) 5681-5722, failed	St L	6276 -3428
DST #3 (Chest) 6098-6104, failed	LTD	6381 -3533
DST #4 (Chest) 6084-6104, failed		

RTD 6380 (St L) Log,

WLT #1 (Chest) 6108 1/2-11, Op 120', R 1200 cc filt wtr, ISIP 1275# /30", IFP 60#, FSIP 50#/NT

WLT #2 (Mrw) 5676 1/2-79, Op 15", R 88.1 CFG + 29,500 cc oil, Gr. 43 deg. + 6200 cc. filt wtr, No ISIP, SP 1750#, FSIP 1750# /30"

DST #5 (L/Mrw) 5825-39 (Strad Pkr) Op 30", R 5' M, ISIP 22#/30" IFP 18#, FFP 18#, FSIP 39#/30"

5 1/2" @ 6019 w/200 sx., CO, Pf 4/5667-68, Sq. 100 sx. 16/5676-80 (Mrw) \$ 20 BO, Ga 3,500,000 Cfgpd/11 hrs, Ga 3,500,000 Cfgpd +

spray oil, NT, Sq 5678-80 w/100 sx, 3 Way jet 5678 (Mrw) 1,200,000 Cfgpd + 1 BOPH, 250A, \$ 1d, Ga 6,640,000 Cfgpd w/spray oil, 1"

Choke, SICP 1100#, SITP 1040#, 16 hr. Ga. 4,735,000 Cfgpd + 1 BOPH,

1" choke, FTP 250#, FCP 650#, 3 hr BD g 2,420 MCF, no fluid
(15/64"ck), FTP 1040, FCP 1120, g 6,640 MCF, 1" ck, SICP
1100, SITP 1040, Morrow 5678, 5/18/64.

LIBERAL ELECTRIC LOG TOPS

2848 KB

Winfield 2675 (+173)

Council Grove 2942 (-94)

Heebner 4196 (-1348)

Toronto 4216 (-1368)

Lansing 4332 (-1484)

Marmaton 5034 (-2186)

Morrow 5608 (-2760)

"S-2" 5654 (-2806) 20/26; DST 8 ~~M~~-; WLTO)&G; ϕ 6,640 MCF

"S-3" 5822 (-2974) 8/12

Chester 5844 (-2986)

c. Sand 6050 (-3202) 6/14

Sand 6106 (-3258) 9/14

Ste. Gen 6162 (-3314)

St. Louis 6276 (-3428)

TD 6380