


WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey Computer Inventoryed
WICHITA BRANCHAPI No. 15 — 077 — 20,691
County NumberS. 23 T. 33S R. 9 E
Loc. 660' FSL & 1980' FWL

County Harper County

Operator Texas Oil & Gas Corp.		640 Acres N	
Address 200 W. Douglas, Suite 300, Wichita, KS 67202			
Well No. #1	Lease Name Hughbanks "A"		
Footage Location 660' feet from XX (S) line		1980' feet from XX (W) line	
Principal Contractor Freeman, Rig #1		Geologist Professional	
Spud Date 6-23-81	Date Completed 7-3-81	Total Depth 4593	P.B.T.D. N/A
Directional Deviation Not directionally drilled		Oil and/or Gas Purchaser N/A	

Elev.: Gr. 1321
DF KB 1333

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8"	24#	344		300	Class "H"

LINER RECORD

PERFORATION RECORD

Top, ft. N/A	Bottom, ft. N/A	Sacks cement N/A	Shots per ft. N/A	Size & type N/A	Depth interval N/A
-----------------	--------------------	---------------------	----------------------	--------------------	-----------------------

TUBING RECORD

Size N/A	Setting depth N/A	Packer set at N/A		
-------------	----------------------	----------------------	--	--

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used N/A	Depth interval treated N/A

INITIAL PRODUCTION

Date of first production D & A, 7-3-81	Producing method (flowing, pumping, gas lift, etc.) dry				
RATE OF PRODUCTION PER 24 HOURS	Oil N/A	Gas bbls. N/A	Water MCF N/A	Gas-oil ratio bbls. N/A	CFPB

Disposition of gas (vented, used on lease or sold) dry, 7-3-81	Producing interval(s) N/A
---	------------------------------

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

FIELD: HUGHBANKS

Operator

Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS,

DRY HOLE, SWDW, ETC.

dry

Well No.

#1

Lease Name

Hughbanks "A"

S 23 T 33S R 9 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

LOG TOPS

Heebner
Dg. Grp.
Iatan
Stalnaker
Kansas City
B/Kansas City
Cherokee
RTD
LTD

Ran O.H. Logs

3396
3429
3676
3744
3996
4208
4376
4593
4593

-2063
-2096
-2343
-2411
-2663
-2875
-3043

DST #1, 3705-50' (Stalnaker), w/results as follows: misrun, pkr. failure

DST #2, 3700-45' (Stalnaker), w/results as follows:

IFP/15": 50-60#, weak blow, dead in 11"

ISIP/110": 1475# (Rig broke down during SI) Rec: 3' DM

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Harold R. Trapp
District Geologist

Signature

Title

July 13, 1981

Date

2625

State Geological Survey
WICHITA BRANCH

Computer Inventoried
KANSAS DRILLERS LOG

API No. 15-077-20,691

COMPANY Texas Oil & Gas Co.

sec. 23 T. 33S R. 9W
Loc. 660' FSL & 1980' FWL

FARM Hughbanks "A" No. 1

COUNTY Harper

ROTARY TOTAL DEPTH 4,593'

COMM. June 23, 1981

COMP. July 3, 1981

CONTRACTOR FREEMAN DRILLING (Rig #1)

ISSUED July 7, 1981

CASING

10 3/4"

8 5/8" Set at 343' cemented w/300 sxs cement

ELEVATION 1,333' K.B.

5 1/2"


4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	1,330'
Sand, Shale and Anhydrite	1,641'
Sand and Shale	1,995'
Lime and Shale	2,500'
Shale	2,738'
Lime and Shale	3,820'
Shale and Sand	3,833'
Lime and Shale	4,593'
Rotary Total Depth	4,593'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

FREEMAN DRILLING COMPANY, INC.


Gary Younger

State of Kansas)
) SS:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 7th day of
July, 1981.

