

13- 34- 1W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AN-SON PETROLEUM CORPORATION
Farm- Bacon No. 1

SEC. 13 T. 34 R. 1W
SW SW SW

Total Depth. 3997'
Comm. 6-6-56 Comp. 6-22-56
Shot or Treated.
Contractor.
Issued. 8-11-56

County Sumner KANSAS



CASING:
8 5/8" 213' csg. cem. w/200 sax.

Elevation. 1162'

Production. Dry

Figures indicate Bottom of Formations

surface & red bed	700
shale & lime	2525
shale	2750
shale & sand	3370
sand & shale	3569
lime	3709
shale & lime	3997
Total Depth	

TOPS: S. T.

Stalnaker	2775
Layton	3185
Kansas City	3345
Marmaton	3543
Mississippi Chat	3903
Mississippi Lime	3990

DRILL STEM TESTS:

- DST #1 3903-38' open 1 hr. strong blow thr-out test. recd. 90' rotary mud, w/very slight salty taste at bottom. Initial & final flow pressure - 0#. S. I. bottom hole pressure in 20 min. - 510#. Hydrostatic - 2115#.
- DST #2 3958-70' open 1 hr. Recd. 15' heavy drlg. mud. Flow pressure - 0#. S. I. bottom hole pressure in 20 min. - 1485#.
- DST #3 3376-92'. open 1 hr. Recd. 6' mud. no show. Flow pressure 0#. S. I. bottom hole pressure in 20 min. - 0# Hydrostatic pressure - 1725#.