


17-34-10W

County Barber
KANSAS



Total Depth. 5361
Comm. 5-23-55
Shot or Treated.
Contractor.
Issued. 8-6-55

Comp. 6-19-55

CASING:
8 5/8 @ 219' w/ 150 sx cmt.

Elevation. 1385

Production. Dry

Figures indicate Bottom of Formations.

red bed & shells	40
red bed & shale	131
shale & shells	219
red rock	445
red bed & shells	995
shale & shells	1695
lime & shale	2040
sandy lime	2140
lime	2180
lime & shale	2480
shale	2565
shale & lime	2870
shale & shells	2995
shale & lime	3070
shale	3170
lime & shale	3255
shale	3335
lime & shale	3377
shale	3440
sand & shale	3511
shale & lime	3540
shale	3620
shale & lime	3690
shale	3840
shale & lime	3910
shale	4005
shale & lime	4075
shale	4164
shale & lime	4235
lime	5030
shale & lime	5054
Viola lime	5095
lime	5112
lime & chert	5130
lime	5141
sand & lime	5226
lime	5260
lime & shale	5331
Arbuckle lime	5361

SCOUT TOPS:

Elgin	3442
Heebner	3621
Toronto	3640
Douglas	3668
Lansing	4028
Stalnaker	4038
Kansas City	4187
Mississippi	4679

Kinderhook	4946
Chattanooga	4997
Maquoketa	5021
Viola	5047
Simpson	5133