


21-34-10W

Total Depth. 5380'  
 Comm- 15-59 Comp. 5-10-59  
 Shot or Treated.  
 Contract Time Drig.  
 Issued. 6-19-65

County Barber  
 KANSAS



CASING:

Elevation. 1352'

8 5/8" 272' cem w/ 200 sx  
 5 1/2" 4760' cem w/ 75 sx

Production. DRY

Figures Indicate Bottom of Formations.

red bed & red rock	160	Cherokee	4585
red bed	850	Mississippi	4694
shale & shells	1490	Viola	5073
anhydrite	1538	Simpson	5152
lime & shale	1700	Simpson shale	5157
lime	1965	Simpson sand	5163
lime & shale	2995	Arbuckle	5320
lime	3189		
lime & shale	3426		
shale & sand	3520		
shale	3595		
shale & lime	3650		
shale	3850	TOPS: SCOUT	
shale & sand	3970	Anhydrite	1490
sand	4063	Lec Lime	3398
shale & lime	4070	Elgin	3418
shale	4145	Heebner	3595
shale & lime	4235	Toronto	3611
lime	4285	Douglas	3638
lime & chert	4324	Stalnaker	3910
lime & shale	4360	Kansas City	4189
lime	4405	Base Kansas City	4421
lime & shale	4440	Marmaton	4489
shale & lime	4485		
lime & shale	4640		
shale & lime	4715		
lime	4719		
lime & chert	4747		
cherty lime	4753		
lime cherty	4813		
cherty lime	4926		
lime & shale strks	4959		
lime & shale	5033		
shale & lime	5080		
lime & shale	5108		
lime, shale, chert	5135		
lime	5158		
shale	5167		
shale & sand	5185		
shale	5167		
shale & sand	5185		
sand & shale	5234		
lime & shale & sand	5261		
sand shale	5290		
shle	5302		
sand & shale	5330		
shale & sand	5358		
Arbuckle	5380	RTD	
Total Depth			