


FORMATION TEST REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

COMPANY GRAVES DRILLING CO., INC. LEASE & WELL NO. BAKER #1 SEC. 10 TWP. 34S RGE. 20W TEST NO. 1 DATE 11/24/88

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE	: 11-24-88	TICKET	: 14441
CUSTOMER	: GRAVES DRILLING CO. INC.	LEASE	: BAKER
WELL	: #1 TEST: 1	GEOLOGIST	: A RATZLAFF
ELEVATION	: 1777 KB	FORMATION	: TORONTO
SECTION	: 10	TOWNSHIP	: 34S
RANGE	: 20W	COUNTY	: COMANCHE
GAUGE SN#	: 4332	STATE	: KANSAS
		RANGE	: 4200
		CLOCK	: 12

INTERVAL FROM	: 4157	TO	: 4226	TOTAL DEPTH	: 4226
DEPTH OF SELECTIVE ZONE	:				
PACKER DEPTH	: 4152	SIZE	: 6.63		
PACKER DEPTH	: 4157	SIZE	: 6.63		
PACKER DEPTH	:	SIZE	:		
PACKER DEPTH	:	SIZE	:		

DRILLING CON.	: PICKRELL		
MUD TYPE	: CHEMICAL	VISCOSITY	: 36
WEIGHT	: 9.4	WATER LOSS (CC)	: 41.0
CHLORIDES (PPM)	: 17000		
JARS-MAKE	: WTC	SERIAL NUMBER	: 421
DID WELL FLOW ?	: NO	REVERSED OUT ?	:

DRILL COLLAR LENGTH	: 205	FT	I.D. inch	: 2.25
WEIGHT PIPE LENGTH	: 0	FT	I.D. inch	: 0.00
DRILL PIPE LENGTH	: 3924	FT	I.D. inch	: 3.80
TEST TOOL LENGTH	: 28	FT	TOOL SIZE	: 5.50
ANCHOR LENGTH	: 69	FT	ANCHOR SIZE	: 5.50
SURFACE CHOKE SIZE	: .75	IN	BOTTOM CHOKE SIZE	: .75
MAIN HOLE SIZE	: 7.875	IN	TOOL JOINT SIZE	: 4.5 XH

BLOW COMMENT #1 : INITIAL FLOW-WEAK BLOW BUILDING TO A 4" BLOW IN
BLOW COMMENT #2 : 15 MINUTES.
BLOW COMMENT #3 : FINAL FLOW-FAIR BLOW TO A GOOD 7" BLOW.
BLOW COMMENT #4 :

RECOVERED : 225 FT OF: SLIGHTLY OIL CUT MUD

Total Barrels Fluid = 1.29
Total Fluid Prod Rate = 23.19 BFPD
Indicated Wtr Rate = 0.23 BWPD

REMARK 1 : TIGHT HOLE !!!
REMARK 2 : ANCHOR = 28 + 41.
REMARK 3 :
REMARK 4 :

SET PACKER(S) :	5:15 PM	TIME STARTED OFF BOTTOM :	8:00 PM
WELL TEMPERATURE :	106		
INITIAL HYDROSTATIC PRESSURE		(A)	2110
INITIAL FLOW PERIOD MIN:	20	(B)	75 PSI TO (C) : 75
INITIAL CLOSED IN PERIOD MIN:	51	(D)	1376
FINAL FLOW PERIOD MIN:	60	(E)	117 PSI TO (F) : 129
FINAL CLOSED IN PERIOD MIN:	48	(G)	1154
FINAL HYDROSTATIC PRESSURE		(H)	1987

WESTERN TESTING CO. INC.
WICHITA-KANSAS

Pressure Transient Report

COMPANY : GRAVES DRILLING CO. INC.
RIG : COMANCHE-KANSAS
FIELD : BAKER
WELL : #1
DATE : 11-24-88
GAUGE NO : 4332

OPERATIONAL COMMENTS

TIGHT HOLE !!!
ANCHOR = 28 + 41.

COMPANY : GRAVES DRILLING CO. INC.
WELL : #1
GAUGE # : 4332
DATE : 24/11/88

FIELD : BAKER
JOB # : 14441
DEPTH : 4226
TEST : TIGHT HOLE !!!

DATA No.	REAL TIME HR:MN:SS	ELAPSE TIME DELTA HOURS	PRESSURE PSIG	TEMP DEG F	DELTA P Pi-P(i-1)
INITIAL FLOW					
2	5:15: 0	0.000	75.000	106.00	0.000
3	5:19:59	0.083	75.000	106.00	0.000
4	5:25: 0	0.167	75.000	106.00	0.000
5	5:30: 0	0.250	75.000	106.00	0.000
6	5:34:59	0.333	75.000	106.00	0.000
INITIAL SHUT-IN					
7	5:37:59	0.383	240.000	106.00	165.000
8	5:40:59	0.433	502.000	106.00	262.000
9	5:43:59	0.483	736.000	106.00	234.000
10	5:46:59	0.533	904.000	106.00	168.000
11	5:49:59	0.583	1014.000	106.00	110.000
12	5:52:59	0.633	1091.000	106.00	77.000
13	5:55:59	0.683	1153.000	106.00	62.000
14	5:58:59	0.733	1200.000	106.00	47.000
15	6: 1:59	0.783	1231.000	106.00	31.000
16	6: 4:59	0.833	1263.000	106.00	32.000
17	6: 7:59	0.883	1285.000	106.00	22.000
18	6:10:59	0.933	1306.000	106.00	21.000
19	6:13:59	0.983	1325.000	106.00	19.000
20	6:16:59	1.033	1340.000	106.00	15.000
21	6:19:59	1.083	1354.000	106.00	14.000
22	6:22:59	1.133	1365.000	106.00	11.000
23	6:25:59	1.183	1376.000	106.00	11.000
FINAL FLOW					
24	6:27: 0	1.200	117.000	106.00	-1259.000
25	6:30:59	1.267	117.000	106.00	0.000
26	6:36: 0	1.350	117.000	106.00	0.000
27	6:40:59	1.433	117.000	106.00	0.000
28	6:45:59	1.517	117.000	106.00	0.000
29	6:51: 0	1.600	118.000	106.00	1.000
30	6:55:59	1.683	119.000	106.00	1.000
31	7: 0:59	1.767	121.000	106.00	2.000
32	7: 6: 0	1.850	123.000	106.00	2.000
33	7:10:59	1.933	125.000	106.00	2.000
34	7:15:59	2.017	127.000	106.00	2.000
35	7:21: 0	2.100	128.000	106.00	1.000
36	7:25:59	2.183	129.000	106.00	1.000
FINAL SHUT-IN					
37	7:28:59	2.233	166.000	106.00	37.000
38	7:31:59	2.283	283.000	106.00	117.000
39	7:34:59	2.333	430.000	106.00	147.000
40	7:37:59	2.383	580.000	106.00	150.000
41	7:40:59	2.433	720.000	106.00	140.000
42	7:43:59	2.483	830.000	106.00	110.000
43	7:46:59	2.533	902.000	106.00	72.000
44	7:49:59	2.583	953.000	106.00	51.000
45	7:52:59	2.633	996.000	106.00	43.000
46	7:55:59	2.683	1024.000	106.00	28.000
47	7:58:59	2.733	1057.000	106.00	33.000
48	8: 1:59	2.783	1080.000	106.00	23.000

COMPANY : GRAVES DRILLING CO. INC.
WELL : #1
GAUGE # : 4332
DATE : 24/11/88

FIELD : BAKER
JOB # : 14441
DEPTH : 4226
TEST : TIGHT HOLE !!!

DATA No.	REAL TIME HR:MN:SS	ELAPSE TIME DELTA HOURS	PRESSURE PSIG	TEMP DEG F	DELTA P Pi-P(1-1)
49	8: 4:59	2.833	1100.000	106.00	20.000
50	8: 7:59	2.883	1120.000	106.00	20.000
51	8:10:59	2.933	1135.000	106.00	15.000
52	8:13:59	2.983	1154.000	106.00	19.000


WESTERN TESTING CO. INC.

4332 DST#1



TK+ # 14441


I




135-20 DST #1

RT # 14441

0



FORMATION TEST REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

COMPANY

GRAVES DRILLING CO. INC.

LEASE & WELL NO.

BAKER #1

SEC. 10 TWP. 34S RGE. 20W TEST NO. 2

DATE 11/26/88

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE	:	11-26-88	TICKET	:	14442
CUSTOMER	:	GRAVES DRILLING CO. INC.	LEASE	:	BAKER
WELL	:	#1 TEST: 2	GEOLOGIST	:	A RATZLAFF
ELEVATION	:	1777 KB	FORMATION	:	SWOPE
SECTION	:	10	TOWNSHIP	:	34S
RANGE	:	20W	STATE	:	KANSAS
GAUGE SN#	:	4332	CLOCK	:	12
		COUNTY :	COMANCHE		
		RANGE :	4200		

INTERVAL FROM	:	4752	TO	:	4770	TOTAL DEPTH	:	4770
DEPTH OF SELECTIVE ZONE	:							
PACKER DEPTH	:	4747	SIZE	:	6.63			
PACKER DEPTH	:	4752	SIZE	:	6.63			
PACKER DEPTH	:		SIZE	:				
PACKER DEPTH	:		SIZE	:				

DRILLING CON.	:	PICKRELL			
MUD TYPE	:	CHEMICAL	VISCOSITY	:	44
WEIGHT	:	9.3	WATER LOSS (CC)	:	10.0
CHLORIDES (PPM)	:	13100			
JARS-MAKE	:	WTC	SERIAL NUMBER	:	421
DID WELL FLOW ?	:	NO	REVERSED OUT ?	:	NO

DRILL COLLAR LENGTH	:	235	FT	I.D. inch	:	2.25
WEIGHT PIPE LENGTH	:	0	FT	I.D. inch	:	0.00
DRILL PIPE LENGTH	:	4489	FT	I.D. inch	:	3.80
TEST TOOL LENGTH	:	28	FT	TOOL SIZE	:	5.50
ANCHOR LENGTH	:	18	FT	ANCHOR SIZE	:	5.50
SURFACE CHOKE SIZE	:	.75	IN	BOTTOM CHOKE SIZE	:	.75
MAIN HOLE SIZE	:	7.875	IN	TOOL JOINT SIZE	:	4.5 XH

BLOW COMMENT #1 : INITIAL FLOW-FAIR BLOW BUILDING TO STRONG IN 12 MINUTES.
BLOW COMMENT #2 : FINAL FLOW-STRONG BLOW.
BLOW COMMENT #3 :
BLOW COMMENT #4 :

RECOVERED : 114 FT OF: SLIGHTLY OIL & GAS CUT MUD
10% GAS-2% OIL-88% MUD

Total Barrels Fluid = 0.56
Total Fluid Prod Rate = 10.76 BFPD
Indicated Oil Rate = 0.22 BOPD
Indicated Wtr Rate = 0.09 BWPD

REMARK 1 : TIGHT HOLE !!!

REMARK 2 : RECOVERED 300 FEET OF GAS ABOVE FLUID.

REMARK 3 :

REMARK 4 :

SET PACKER(S) : 10:30 AM

TIME STARTED OFF BOTTOM : 1:15 PM

WELL TEMPERATURE : 118

INITIAL HYDROSTATIC PRESSURE

(A) 2370

INITIAL FLOW PERIOD MIN: 15

(B) 97 PSI TO (C) : 97

INITIAL CLOSED IN PERIOD MIN: 42

(D) 229

FINAL FLOW PERIOD MIN: 60

(E) 99 PSI TO (F) : 99

FINAL CLOSED IN PERIOD MIN: 45

(G) 163

FINAL HYDROSTATIC PRESSURE

(H) 2340

WESTERN TESTING CO. INC.
WICHITA-KANSAS

Pressure Transient Report

COMPANY : GRAVES DRILLING CO. INC.
RIG : COMANCHE-KANSAS
FIELD : BAKER
WELL : #1
DATE : 11-26-88
GAUGE NO : 4332

OPERATIONAL COMMENTS

TIGHT HOLE !!!
RECOVERED 300 FEET OF GAS ABOVE FLUID.

COMPANY : GRAVES DRILLING CO. INC.
 WELL : #1
 GAUGE # : 4332
 DATE : 26/11/88

FIELD : BAKER
 JOB # : 14442
 DEPTH : 4770
 TEST : TIGHT HOLE !!!


DATA No.	REAL TIME HR:MN:SS	ELAPSE TIME DELTA HOURS	PRESSURE PSIG	TEMP DEG F	DELTA P Pi-P(i-1)
INITIAL FLOW					
2	10:30: 0	0.000	97.000	118.00	0.000
3	10:34:59	0.083	97.000	118.00	0.000
4	10:40: 0	0.167	97.000	118.00	0.000
5	10:45: 0	0.250	97.000	118.00	0.000
INITIAL SHUT-IN					
6	10:48: 0	0.300	100.000	118.00	3.000
7	10:51: 0	0.350	111.000	118.00	11.000
8	10:54: 0	0.400	125.000	118.00	14.000
9	10:57: 0	0.450	139.000	118.00	14.000
10	11: 0: 0	0.500	153.000	118.00	14.000
11	11: 3: 0	0.550	160.000	118.00	7.000
12	11: 6: 0	0.600	168.000	118.00	8.000
13	11: 9: 0	0.650	176.000	118.00	8.000
14	11:12: 0	0.700	183.000	118.00	7.000
15	11:15: 0	0.750	192.000	118.00	9.000
16	11:18: 0	0.800	202.000	118.00	10.000
17	11:21: 0	0.850	213.000	118.00	11.000
18	11:24: 0	0.900	222.000	118.00	9.000
19	11:27: 0	0.950	229.000	118.00	7.000
FINAL FLOW					
20	11:28: 0	0.967	99.000	118.00	-130.000
21	11:31:59	1.033	99.000	118.00	0.000
22	11:37: 0	1.117	99.000	118.00	0.000
23	11:42: 0	1.200	99.000	118.00	0.000
24	11:46:59	1.283	99.000	118.00	0.000
25	11:52: 0	1.367	99.000	118.00	0.000
26	11:57: 0	1.450	99.000	118.00	0.000
27	12: 1:59	1.533	99.000	118.00	0.000
28	12: 7: 0	1.617	99.000	118.00	0.000
29	12:12: 0	1.700	99.000	118.00	0.000
30	12:16:59	1.783	99.000	118.00	0.000
31	12:22: 0	1.867	99.000	118.00	0.000
32	12:27: 0	1.950	99.000	118.00	0.000
FINAL SHUT-IN					
33	12:30: 0	2.000	99.000	118.00	0.000
34	12:33: 0	2.050	100.000	118.00	1.000
35	12:36: 0	2.100	102.000	118.00	2.000
36	12:39: 0	2.150	104.000	118.00	2.000
37	12:42: 0	2.200	107.000	118.00	3.000
38	12:45: 0	2.250	111.000	118.00	4.000
39	12:48: 0	2.300	116.000	118.00	5.000
40	12:51: 0	2.350	122.000	118.00	6.000
41	12:54: 0	2.400	128.000	118.00	6.000
42	12:57: 0	2.450	135.000	118.00	7.000
43	13: 0: 0	2.500	142.000	118.00	7.000
44	13: 3: 0	2.550	150.000	118.00	8.000
45	13: 6: 0	2.600	155.000	118.00	5.000
46	13: 9: 0	2.650	160.000	118.00	5.000
47	13:12: 0	2.700	163.000	118.00	3.000

4332 DST #2

*


TK+ # 14442

I




13520 DST #2

TKT # 15442



FORMATION TEST REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE	: 11-27-88	TICKET	: 14443
CUSTOMER	: GRAVES DRILLING CO. INC.	LEASE	: BAKER
WELL	: #1 TEST: 3	GEOLOGIST	: A RATZLAFF
ELEVATION	: 1777 KB	FORMATION	: MISSISSIPPI
SECTION	: 10	TOWNSHIP	: 34S
RANGE	: 20W	STATE	: KANSAS
GAUGE SN#	: 4332	CLOCK	: 12
COUNTY	: COMANCHE		
RANGE	: 4200		

INTERVAL FROM	: 5134	TO	: 5190	TOTAL DEPTH	: 5190
DEPTH OF SELECTIVE ZONE	:				
PACKER DEPTH	: 5129	SIZE	: 6.63		
PACKER DEPTH	: 5134	SIZE	: 6.63		
PACKER DEPTH	:	SIZE	:		
PACKER DEPTH	:	SIZE	:		

DRILLING CON.	: PICKRELL		
MUD TYPE	: CHEMICAL	VISCOSITY	: 39
WEIGHT	: 9.2	WATER LOSS (CC)	: 11.2
CHLORIDES (PPM)	: 14500		
JARS-MAKE	: WTC	SERIAL NUMBER	: 421
DID WELL FLOW ?	: NO	REVERSED OUT ?	: NO

DRILL COLLAR LENGTH	: 205	FT	I.D. inch	: 2.25
WEIGHT PIPE LENGTH	: 0	FT	I.D. inch	: 0.00
DRILL PIPE LENGTH	: 4901	FT	I.D. inch	: 3.80
TEST TOOL LENGTH	: 28	FT	TOOL SIZE	: 5.50
ANCHOR LENGTH	: 56	FT	ANCHOR SIZE	: 5.50
SURFACE CHOKE SIZE	: .75	IN	BOTTOM CHOKE SIZE	: .75
MAIN HOLE SIZE	: 7.875	IN	TOOL JOINT SIZE	: 4.5 XH

BLOW COMMENT #1 : STRONG BLOW ON THE INITIAL FLOW-GAS TO SURFACE DURING
BLOW COMMENT #2 : THE INITIAL SHUT-IN. SEE ATTACHED FLOW CHART.
BLOW COMMENT #3 :
BLOW COMMENT #4 :

RECOVERED : 210 FT OF: THIN GAS CUT MUD

Total Barrels Fluid = 1.08
Total Fluid Prod Rate = 20.70 BFPD
Indicated Wtr Rate = 0.21 BWPD

REMARK 1 : TIGHT HOLE !!
REMARK 2 : ANCHOR = 28 + 28
REMARK 3 :
REMARK 4 :

SET PACKER(S) : 2:55 AM

TIME STARTED OFF BOTTOM : 5:40 AM

WELL TEMPERATURE : 126

INITIAL HYDROSTATIC PRESSURE

INITIAL FLOW PERIOD MIN: 15

INITIAL CLOSED IN PERIOD MIN: 51

FINAL FLOW PERIOD MIN: 60

FINAL CLOSED IN PERIOD MIN: 48

FINAL HYDROSTATIC PRESSURE

(A) 2536

(B) 94 PSI TO (C) : 94

(D) 1838

(E) 94 PSI TO (F) : 94

(G) 1702

(H) 2497

GAS FLOW REPORT

Date : 11-27-88	Ticket # : 14443
Customer : GRAVES DRILLING CO. INC.	Lease : BAKER
Well : #1 Test : 3	Geologist : A RATZLAFF
Elevation (KB) : 1777	Formation : MISSISSIPPI
Section : 10	Township : 34S
Range : 20W	County : COMANCHE
Gauge SN # : 4332	State : KANSAS
	Range : 4200
	Clock : 12

TIME GAUGE (MIN)	TESTER TYPE	ORFICE SIZE	PRESSURE (PSI)	FLOW DESCRIPTION
---------------------	-------------	----------------	-------------------	------------------

PRE FLOW
=====

SECOND FLOW
=====

10	MERLA	3/4"	15" of WTR	55200 CFPD
20			15	55200 CFPD
30			15	55200 CFPD
40			15	55200 CFPD
50			15	55200 CFPD
60			15	55200 CFPD

Gas Bottle SN # : 20 P
Date Bottle Filled : 11-27-88
Date to be Invoiced :

WESTERN TESTING CO. INC.
WICHITA-KANSAS

Pressure Transient Report

COMPANY : GRAVES DRILLING CO. INC.
RIG : COMANCHE-KANSAS
FIELD : BAKER
WELL : #1
DATE : 11-27-88
GAUGE NO : 4332

OPERATIONAL COMMENTS

TIGHT HOLE !!
ANCHOR = 28 + 28

COMPANY : GRAVES DRILLING CO. INC.
WELL : #1
GAUGE # : 4332
DATE : 27/11/88

FIELD : BAKER
JOB # : 14443
DEPTH : 5190
TEST : TIGHT HOLE !!

DATA No.	REAL TIME HR:MN:SS	ELAPSE TIME DELTA HOURS	PRESSURE PSIG	TEMP DEG F	DELTA P Pi-P(i-1)
INITIAL FLOW					
2	2:55: 0	0.000	94.000	126.00	0.000
3	2:59:59	0.083	94.000	126.00	0.000
4	3: 5: 0	0.167	94.000	126.00	0.000
5	3:10: 0	0.250	94.000	126.00	0.000
INITIAL SHUT-IN					
6	3:13: 0	0.300	318.000	126.00	224.000
7	3:16: 0	0.350	542.000	126.00	224.000
8	3:19: 0	0.400	738.000	126.00	196.000
9	3:22: 0	0.450	935.000	126.00	197.000
10	3:25: 0	0.500	1134.000	126.00	199.000
11	3:28: 0	0.550	1323.000	126.00	189.000
12	3:31: 0	0.600	1472.000	126.00	149.000
13	3:34: 0	0.650	1572.000	126.00	100.000
14	3:37: 0	0.700	1644.000	126.00	72.000
15	3:40: 0	0.750	1697.000	126.00	53.000
16	3:43: 0	0.800	1733.000	126.00	36.000
17	3:46: 0	0.850	1762.000	126.00	29.000
18	3:49: 0	0.900	1783.000	126.00	21.000
19	3:52: 0	0.950	1802.000	126.00	19.000
20	3:55: 0	1.000	1816.000	126.00	14.000
21	3:58: 0	1.050	1828.000	126.00	12.000
22	4: 1: 0	1.100	1838.000	126.00	10.000
FINAL FLOW					
23	4: 2: 0	1.117	94.000	126.00	-1744.000
24	4: 5:59	1.183	94.000	126.00	0.000
25	4:11: 0	1.267	94.000	126.00	0.000
26	4:16: 0	1.350	94.000	126.00	0.000
27	4:20:59	1.433	94.000	126.00	0.000
28	4:26: 0	1.517	94.000	126.00	0.000
29	4:31: 0	1.600	94.000	126.00	0.000
30	4:35:59	1.683	94.000	126.00	0.000
31	4:41: 0	1.767	94.000	126.00	0.000
32	4:46: 0	1.850	94.000	126.00	0.000
33	4:50:59	1.933	94.000	126.00	0.000
34	4:56: 0	2.017	94.000	126.00	0.000
35	5: 1: 0	2.100	94.000	126.00	0.000
FINAL SHUT-IN					
36	5: 3:59	2.150	424.000	126.00	330.000
37	5: 6:59	2.200	663.000	126.00	239.000
38	5:10: 0	2.250	857.000	126.00	194.000
39	5:13: 0	2.300	1029.000	126.00	172.000
40	5:16: 0	2.350	1178.000	126.00	149.000
41	5:18:59	2.400	1306.000	126.00	128.000
42	5:21:59	2.450	1400.000	126.00	94.000
43	5:25: 0	2.500	1474.000	126.00	74.000
44	5:28: 0	2.550	1527.000	126.00	53.000
45	5:31: 0	2.600	1569.000	126.00	42.000
46	5:33:59	2.650	1599.000	126.00	30.000
47	5:36:59	2.700	1627.000	126.00	28.000
48	5:40: 0	2.750	1654.000	126.00	27.000

COMPANY : GRAVES DRILLING CO. INC.
WELL : #1
GAUGE # : 4332
DATE : 27/11/88


FIELD : BAKER
JOB # : 14443
DEPTH : 5190
TEST : TIGHT HOLE !!

DATA No.	REAL TIME HR:MN:SS	ELAPSE TIME DELTA HOURS	PRESSURE PSIG	TEMP DEG F	DELTA P Pi-P(i-1)
49	5:43: 0	2.800	1673.000	126.00	19.000
50	5:46: 0	2.850	1688.000	126.00	15.000
51	5:48:59	2.900	1702.000	126.00	14.000

WESTERN TESTING CO. INC.

332 DST#3

TKT # 14443



13520 DST#3

TKT # 14443

