

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

11-34-11W

Company- RUPP-FERGUSON  
Farm- Koontz

No. 1

SEC. 11 T. 34 R. 11W  
NW NW NE

Total Depth. 5214'

Comm. 7-11-54

Comp. 8-4-54


Shot or Treated.

Contractor. Rupp-Ferguson Oil Co.

Issued. 9-11-54

County Barber

KANSAS



Elevation. 1109' KB

Production. Dry

CASING:

10 3/4" 252' cem w/200 sx  
5 1/2" 4761' cem w/150 sx

Figures indicate Bottom of Formations.

red bed & shells	470
red rock, shale & shells	811
shale & shells	850
anhydrite broken	895
shale & shells	1340
salt	1450
shale & shells	1535
shale & lime	3503
sand & shale	3576
sand, lime & shale	3635
lime & shale	3702
sand & shale	3712
lime & shale	4219
lime	4448
lime & shale	4576
chert & lime	4598
chert	4647
cherty lime & shale	4738
shale & lime	4881
Viola	4979
Simpson	5008
sandstone	5020
sand & shale	5105
shale	5139
sand-shale	5176
Arbuckle	5214
Total Depth	

Tops:

Elgin Sand	3503
Douglas Sand Zone	3702
Sand (Layton equivalent)	4030
Kansas City Lime	4150
Mississippian	4576
Kinderhook Shale	4744
Chattanooga Shale	4847
Misener Sand	4873
Viola Lime	4880
Simpson	4979
Simpson Sand	5000
Arbuckle Dolomite	5176

Perf. 33/4606-14, rec. 12' fluid, 90% water, 10% oil & BS 1st hr.  
 Rec. 25' fluid, 90% water, 10% oil & BS 2nd hr.  
 Rec. 28' fluid, 65% water, 35% oil & BS 3rd hr.  
 Hydrafrac, rec. 20 BFPH, 90% water, 10% oil. Squeezed.  
 Perf. 32/4580-88. Rec. 5' fluid, 90% water, 10% oil 1st hr.  
 Rec. 12' fluid, 90% water, 10% oil 2nd hr.  
 Rec. 3 gal. fluid, 90% water 3rd hr. Rec. trace water only 4th hr.  
 Hydrafrac, rec. 5-10 BFPH.

Dry and abandoned