


~~25~~ 25-34-11W

County Barber
 KANSAS



Total Depth. 5225'
 Comm. 1-24-58 Comp. 2-13-58
 Shot or Treated.
 Contractor. Honaker-Davis Drilg. Co.
 Issued. 4-19-58

Elevation. 1336' RB

Production. Dry

CASING:

8 5/8" 240' w/200 sx cem.

Figures indicate Bottom of Formations.

soil, clay	40
red rock, sand	160
red rock	270
red rock, shale	545
shale, red bed	730
gyp, shale	840
shale, shells	1220
shale, gyp	1520
shale, lime	2395
shale, shells	2575
shale, lime, shalle	2760
shale, lime	2842
shale, shells	3065
shale, lime	3510
shale, shells	3575
shale, lime shells	3639
shale, lime	3788
shale, shells	3870
shale, sand	4070
shale, shells	4135
shale, lime	4220
lime	4415
lime, shale	4535
lime	4580
shale, lime	4712
lime, chert	4750
lime	4827
lime, chert	4868
lime	4940
shale, lime	5022
lime	5080
lime, shale	5138
lime, chert	5187
shale, lime	5225
Rotary Total Depth	

DST #3; 4730-4750'--open 20"-
 35" - 20". Blow weak 17# & 2".
 Rec. 70' mud, IBHP-530#, FBHP-
 140#.

TOPS:	
Elgin sand	3523
Heebner	3634
Stalnaker sand	3945
Kansas City	4214
Mississippian	4704
Kinderhook	5014
Chattanooga	5040
Misener sand	5064
Maquoketa	5066
Viola	5100
Simpson shale	5190
Simpson Sand	5198

DST #1: 3939-3957' Open 20"-
 60"-20". Blow: Fair. Rec. 570'
 wtr., IBHP-1730#, FBHP-1610#,
 IFP-30#, FFP-310#.

DST #2: 4714-4730--Open 20"-
 30" - 20". Blow weak 7" & 2".
 Rec. 30' mud, IBHP-120#, FBHP-
 110#.