

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


26-34-11W

Company- D. R. LAUCK OIL & SUNRAY MID-CONT. OIL
Farm- Elliott No. 1

SEC. 26 T. 34 R. 11W
SE SW SW

Total Depth. 4715'
Comm. 3-4-59 Comp. 3-18-59
Shot or Treated.
Contractor. D. R. Lauck Drlg.
Issued. 7-11-59

County Barber
KANSAS



CASING:

8 5/8" 203' cem w/160 sx.

Elevation. 1307' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand	30
red bed & shells	203
red bed	250
shale & red bed	815
shale & shells	1200
Anhydrite	1430
lime & shale	1665
lime	1885
lime & shale	2190
lime, shale & red bed	2285
shale & shells	2535
shale	2815
lime & shale	2930
shale & shells	3150
lime & shale	3300
brown lime & shale	3480
shale & lime	3895
shale & sand	4015
sand	4030
shale	4160
shale & lime	4289
lime	4415
shale & lime	4495
lime & shale	4560
shale & lime	4620
lime & shale	4655
lime	4715 RTD
Total Depth	

DST #4 4665-4680', op 1 hr, fair blow
1 hr, rec. 90' oil cut mud; Missed ISIP
by sliding tool lost 10' to bottom; bottom
chart showed plugging action thruout test.
IFP 45#, FFP 60#, FSIP 1170#/30 min, still
building.

TOPS:	SAMPLE	ELECTRIC
Heebner	3609	3609
Toronto	3624	3622
Douglas	3649	3648
Haskell	3862	3860
Stalnaker	3923	3920
Kansas City	4181	4182
Base Kansas City	4402	4398
Mississippian	4638	4636

DST #1 3925-3940', op 1 hr, fair blow 1
hr. rec. 30' watery mud, 420' salt water,
ISIP 1685#/20", FSIP 1565#/20", IFP 35#.
FFP 225#.

DST #2 4640-4655', op 1 hr, gas to surf.
in 5 min. Gauged 537,000 CFG 5 min,
546,000 CFG 10 min, 460,000 CFG 20 min,
416,000 CFG 30 min, 391,000 CFG 40 min,
391,000 CFG 50 min, 391,000 CFG 60 min,
rec. 25' mud, ISIP 1905#/30", IFP 48#,
FFP 30#, FSIP 1858#/30".

DST #3 4655-4665', op 1 hr, good blow 1 hr,
gas to surf. in 3½ min. Gauged 240,000
CFG 2 min, 167,000 CFG 10 min, 155,000
CFG 20 min, 155,000 CFG 30 min, 139,000
CFG 40 min, 139,000 CFG 50 min, 139,000
CFG 60 min, rec. 25' mud, ISIP 1920#/20",
IFP 30#, FFP 15#, FSIP 1858#/20".