


4-106W MAP NO. SEC 11-34S-22W  
 STATE Kans COUNTY Clark LOC 50' W of C of Sec  
 OPER. Graham-Michaelis Drlg. Co. - Wichita, Ks. PY/FR  
 WELL 1-11 FARM Randall FT/FR  
 POOL Snake Creek W (Mrw O/G) ELEV. ~~1839~~ <sup>1831</sup> GR. ~~1846~~ <sup>1838</sup> d849 KB  
 CON. Co. tools GEOL. John James  
 CO. INT.  
 F.R. 2-5-65 SPUD 2-5-65 COMP 4-8-65  
 TD ~~558~~ 528 FM Chest sd PBTD  
 COMP. RECORD Mrw 5378-94 64 1000A & Frac  
 Co Ga 15,350,000 Cfgpd  
 8 5/8" @598 w/300 sx. 4 1/2" @5527 w/125 sx.



*Dates Inc.*

(KB Log)	DST #1 (Mrw sd) 5346-5400, Op 25", GTS/
Lans 4420 -2571	1 1/2", Ga 6,352,000 Cfgpd/10", Ga 7,780,000
Mrw sh 5323T-3474	Cfgpd/20" & Stab. R 30' dist & GCM, ISIP
Mrw sd 5376T-3527	1726#/30", IFP 1314#, FFP 1337#, FSIP
Ches sh 5410T-3561	1726#/30"
Ches sd 5466T-3617	DST #2 (Chest sh) 5413-38, Op 30", R 3'
LTD NA	M, ISIP 114#/30", IFP 32#, FFP 32#, FSIP
RTD 5528 -3409	32#/30"
	DST #3 (Chest sd) 5445-95, Op 30", R 10'
	M, ISIP 894#/30", IFP 72#, FFP 97#, FSIP

312#/30", RTD 5528, Ran Log, 4 1/2" @5527 w/125 sx., MICT, Pf 64/  
 5378-94 (Mrw), 1000A & Frac 15,000 gal flu x15,000# sd, Ga  
 5,600,000 Cfgpd & spray LW thru 2" tbg, SI/NT, Ga 15,350,000  
 Cfgpd thru csg  
 Co Ga 15,350,000 Cfgpd, No SIP, Mrw 5378-94 - COMPLETED (4-5-65)