

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

6-34-12W

Company-AYLWARD DRILLING CO.
Farm-Donovan "B" No. 1

SEC. 6 T. 34 R. 12W
NE SW SW

Total Depth. 4723

Comm. 2-21-56


Comp. 3-5-56

Shot or Treated. Perf. 135/4678-4705, Sandfrac. w/ 10,000# sand,
Contractor. Aylward Drilling Co. 10,000 gal Petrojel.

Issued. 4-28-56

County Barber

KANSAS



CASING:

8 5/8 @ 195' w/ 150 sx cmt.
5 1/2 @ 4723' w/ 100 sx cmt.

Elevation. 1557 RB

Production. 21,500,000 CF/CPD

Figures indicate Bottom of Formations.

red bed	60
red bed & sand	160
red bed & shale	770
red rock, lime, shale & shells	1370
salt, red rock & shale	1775
lime & shale streaks	1946
lime & shale	2205
shale	2215
lime & shale	2305
shale, little lime	2520
lime & shale	2613
shale	2735
shale, little lime	2940
lime & shale	3275
lime	3310
lime & shale	3340
lime	3370
lime & shale	3553
sand	3750
lime & shale	3896
shale & sand	4023
lime & shale	4090
lime	4206
broken lime	4279
lime	4310
lime, some shale	4380
lime	4425
lime & shale	4471
lime & shale	4665
Mississippian	4723
Total Depth	

TOPS:

Elgin sand	3608
Heebner	3796
Lansing	3998
Mississippian	4660

DST #1: 4660-90, open 1 hr. gas in
3 min. 1,890 MCF, FP 370-520#, BHP
1690#

DST #2: 4690-4713, open 45 min. gas
in 1 min. 3,970 MCF, FP 970-1000#,
BHP 1720#