

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Plotted
8-34-12W


Company - J. M. HUBER CORP. et al
Farm - Cook No. 1

SEC. 8 T. 34 R. 12W
CW $\frac{1}{2}$ SW NW

Total Depth. 5459'
Comm. 1-31-47 Comp. 3-3-47
Spct or Treated.
Contractor. J. M. Huber Corp.
Issued. 3-29-47

County. Barber

KANSAS



Elevation. 1502 ft

CASING:
10" 478' cem. w/ 250 sx.

Production. Dry

Figures Indicate Bottom of Formations.

red bed 200
red bed & shells 478
red bed shale & shells 645
shale & shells 1250
salt & shale & shells 1400
lime & shale 1730
lime 1808
lime & shale 1970
lime & shale strks 2040
lime & shale 2165
lime brkn 2180
lime & shale strks 2250
lime & shale 2890
shale & lime strks 2995
lime & shale 3145
lime, strks of shale 3220
lime & shale 3355
lime & shale strks 3425
shale & lime strks 3500
shale & lime 3546
sand 3590
sand & shale 3670
shale & sand 3695
sand 3742
shale 3820
sand limo 3845
lime & shale 4025
lime 4175
lime & shale 4310
lime 4500
lime & shale 4700
limo 4745
cherty lime 4780
lime 4980
lime & shale 5030
shale 5122
lime 5164
lime & chert strks 5185
lime 5216
sand & shale strks 5231

Top Chattanooga 5076
" Misnor 5114
" Viola 5115
" Simpson 5216
" Arbuckle 5417

Halliburton Drill stem test
5216-31, Open 15 Min. recovered
170' mud & 1000' salt wtr.

Fair porosity from 5421-5425 &
from 5435-5438, no shows. Ran
Schlumberger.

sand 5253
sand & shale 5301
shale & sand strks 5344
shale & sand 5395
sand & shale 5444
lime 5459
Total Depth

Tops:
Ft. Riley 2070
Base Florence Flint 2195
Base Wroford 2295
Base Oread 3858
Top Lansing 3974
" Mississippi 4670
Base Mississippi 5002

