

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

17-34-12W

Company. MAGNOLIA PETROLEUM CO.
Farm. V. L. Cook No. 1

SEC. 17 T. 34 R. 12W
NW NE SE

Total Depth. 4795

Comm. 2-28-56

Comp. 3-25-56


Shot or Treated.

Contractor. Graham-Messman-Rinehart Drilling Co.

Issued. 8-18-56

County Barber

KANSAS



Elevation. 1497 DE

Production. 2,050,000 CFGPD

CASING:
9 5/8 @ 357' w/ 300 sx cmt.
5 1/2 @ 4794' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

surface hole	358
shale	1230
shale & lime	2779
shale	2950
lime & shale	3112
shale & sand	3376
shale & lime	3605
shale & sand	3793
lime & shale	4105
lime	4165
lime & shale	4258
lime	4475
lime & shale	4550
lime	4643
lime & shale	4694
lime	4745
chert	4765
Mississippi	4795
Total Depth	

TOPS:

Elgin sand	3603
Heebner	3833
Douglas	3885
Lansing-KC	4029
Mississippi chat	4721

DST #1: 4720-65, open 1 hr good bl.
thruout, rec: 45' DM, IFP 35#, FFP
35#, BHP 215#/20 min.