

508 East Murdock,

Wichita, Kansas

19-34-12W

Company- CARTER OIL CO.

Farm- R. B. Cook

No. 1

SEC.

19

T. 34

R. 12W

NW SE NE

Total Depth. 4880'

Comm. 10-8-55

Comp. 10-29-55

Shot or Treated.


Contractor.

Issued. 5-24-58

County

Barber

KANSAS



Elevation. 1547'

Production. 3,600,000 CFG

CASING:

8 5/8" 277' cem w/250 sx.

5 1/2" 4880' cem w/250 sx.

Figures indicate Bottom of Formations.

red shale	189
red bed	277
red bed & shale	628
shale	1300
shale & shells	1422
shale	1530
Anhydrite	1565
shale	1750
lime	1881
lime & shale	2005
shale & shells	2210
lime & shale	2338
lime	2415
shale & lime	3030
lime & shale	3224
shale & lime	3400
lime	3425
lime & shale	3614
shale	3625
sand	3765
sand & shale	3818
shale & lime	3968
lime & shale	3998
shale & lime	4106
lime	4194
lime & shale	4292
lime	4571
lime & shale	4682
lime	4712
lime & shale	4791
lime	4880
Total Depth	

TOPS: SCOUT

Elgin	3623
Heebner	3864
Lansing	4065
Marmaton	4640
Burgess Zone	4756
Mississippi	4781

DST #1 Packer @ 3624' TD 3796', tool open
1 hr, good blow thruout, rec. 2820'
of slight gas cut salt water. IFP
900#, FFP 1500#, BHSIP 1600# in
30 mins.

DST #2 Packer set at 4775', TD 4828', open

1 hr, gas to surface in 1 min. At

end of 5 min, by Spring gauge 7,600

MCF, end of 7 min, Spring gauge

8,500 MCF, end of 20 mins by Spring gauge

9,100 MCF end of 45 min spring gauge

8,060 MCF, end of 1 hr, Spring gauge

8,060 MCF, IFP 815# FFP 680#,

BHSIP 1740#.