

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

19-34-12W

Company- MAGNOLIA PETROLEUM CO.
Farm- C Olson "B" No. 1

SEC. 19 T. 34 R. 12W
NE SW SW

Total Depth. 4855

Comm. 12-31-55

Comp. 1-26-56


Shot or Treated.

Contractor. Graham-Messman-Rinehart Drilling Co.

Issued. 5-5-56

County Barber

KANSAS



Elevation. 1501

Production. 30,500,000 CFGPD

CASING:

9 5/8 @ 355' w/ 300 sx cmt.
5 1/2 @ 4854' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

shale	1750
shale & lime	2134
shale	2498
shale & lime	3706
lime	3905
shale & lime	4017
lime	4855
Total Depth	

TOPS:

Elgin	3621
Heebner	3855
Lansing	4058
Kansas City	4354
Mississippi	4755

DST #1: 4755-4801 (corr. meas.) open
1 hr. gas in 1 3/4 min. ga. 6,448
MCFGPD in 15 min, 6,640 MCFGPD in
30 min, leveled off at 6928 MCFGPD
in 45 & 60 min. rec. 28' G & distillate
CM, FP 1070-1470#, BHP 1793#/20 min.

DST #2: 4820-55, open 1 hr. wk. stdy
bl. thruout; rec. 118' DM, 60' wtry
mud w/ VSSO, FP 30-80#, BHP 1890#/
20 min.