

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

20-34-12W

Company. MAGNOLIA PETROLEUM CO.
Farm. R. B. Cook No. 2

SEC. 20 T. 34 R. 12W
SW NE NW

Total Depth. 4853'

Comm. 12-4-55

Comp. 1-18-56


Shot or Treated.

Contractor. Graham-Messman-Rinehart Oil

Issued. 5-26-56

County Barber

KANSAS



CASING:

9 5/8" 354' cem w/300 sx
5 1/2" 4852' cem w/150 sx

Elevation. 1534'

Production. Calc. OF 4,200,000
CFG/PD

Figures indicate Bottom of Formations

shale	145
shale & gyp	355
shale	1710
shale & lime	3580
sand shale	3835
shale	3915
shale & lime	4190
lime	4298
shale & lime	4402
lime	4637
shale & lime	4688
lime	4780
Miss. chert	4828
Miss. lime	4836
Miss.	4853
Total Depth	

Tops:

Elgin Sand	3619
Heebner	3859
Lansing	4052
Kansas City	4361
Burgess Sand	4744
Mississippi Chert	4756

(corrected interval)

DST #1 4758-83' open 1 hr., gas in 3 min., ga. 1020
MCFG/D in 5 min., 887 MCFG/D in 15 mins., 375 MCFG/D
in 30 min., 175 MCFG/D in 45 min., 130 MCFG/D in
60 min., rec. 55' GCM, FP 330 - 0#, BHP 285#/20 min.