

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

20-34-12W

Company. MAGNOLIA PETROLEUM CO.
Farm- C. Olson No. 1

SEC. 20 T. 34 R. 12W
SW NE SW


Total Depth. 4865
Comm. 10-8-55

Comp. 11-10-55

County Barber
KANSAS

Shot or Treated.

Contractor. Graham-Messman-Rinehart Oil Co.
issued. 2-11-56



CASING:
9 5/8 @ 355' w/ 300 sx cmt.
5 1/2 @ 4862' w/ 200 sx cmt.

Elevation. 1503 DF

Production. 35,500,000 CFGPD

Figures indicate Bottom of Formations.

sand, clay & red bed	356
red bed & shale	1110
shale	1773
lime & shale	1949
shale & gypsum	2120
lime & shale	4205
lime	4264
lime & shale	4409
lime	4444
lime & shale	4495
lime	4587
shale & lime	4636
lime	4798
Mississippi	4865
Total Depth	

TOPS:
Lansing 4023
Hardtner sand 4718
Mississippian 4735

DST #1: 4735-60, open 1 hr. gas to
surf. 8 min. ga. 360 MCF, rec. 50'
GCM, BHP 1760#/20 min.

DST #2: 4760-4841, open 1 hr. gas in
3 min. ga. 1020 MCF/5 min. 2740 MCF/
1 hr. rec. 160' GCM, FP 160-350#,
BHP 1815#/20 min.

DST #3: 4830-65, open 1 hr. wk. bl.
thruout, rec. 30' SGC wtry mud, FP
30-30#, BHP 142#/20 min.